

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

001

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: U-015630-ST	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT	
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company				9. WELL NAME and NUMBER: NBU 438	
3. ADDRESS OF OPERATOR: P.O. Box 1148 CITY Vernal STATE UT ZIP 84078			PHONE NUMBER: (435) 781-7023	10. FIELD AND POOL, OR WILDCAT: Natural Buttes	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2133' FNL & 986' FWL AT PROPOSED PRODUCING ZONE:				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 13.9 Miles Northeast of Ouray, UT				12. COUNTY: Uintah	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 986'		16. NUMBER OF ACRES IN LEASE: 285.20		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) Refer to Topo C		19. PROPOSED DEPTH: 8,600		20. BOND DESCRIPTION: 400JU0705	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 4954.6' GL		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION: 10 Days	

**PROPOSED CASING AND CEMENTING PROGRAM**

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
11-12 1/4	9 5/8 or 8 5/8	250	Refer to 10 pt program
7 7/8	4 1/2 or 5 1/2	8,600	Refer to 10 pt program

**CONFIDENTIAL**

**ATTACHMENTS**

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- ☒ WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER  
☐ EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER

- ☒ COMPLETE DRILLING PLAN  
☐ FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

**RECEIVED**

NAME (PLEASE PRINT) Cheryl Cameron

TITLE Operations

NOV 22 2002

SIGNATURE

DATE 11/19/2002


DIVISION OF

OIL, GAS AND MINING

(This space for State use only)


API NUMBER ASSIGNED: 43-047-3487

APPROVAL:

**Approved by the  
Utah Division of  
Oil, Gas and Mining**  
Date: 01-29-03  
By: 

T9S, R21E, S.L.B.&M.

Set Stone,  
UELS Alum. Cap  
on 5/8" Rebar



**LEGEND:**

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

LATITUDE = 39°59'38"  
LONGITUDE = 109°33'45"

**BASIS OF BEARINGS**


BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

**EL PASO  
PRODUCTION OIL & GAS COMPANY**

Well location, NBU #438, located as shown in the SW 1/4 NW 1/4 of Section 33, T9S, R21E, S.L.B.&M. Uintah County, Utah.

**BASIS OF ELEVATION**

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



**CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*Robert H. Kay*  
REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319 L.  
STATE OF UTAH  
KAY

**UINTAH ENGINEERING & LAND SURVEYING**

85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 1-4-02	DATE DRAWN: 1-9-02
PARTY G.S. K.S. P.M.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE	EL PASO PRODUCTION OIL & GAS COMPANY

**STATE OF UTAH**  
**DEPARTMENT OF NATURAL RESOURCES**  
**DIVISION OF OIL, GAS AND MINING**

002

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b> Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT -- for such proposals		6. Lease Designation and Serial Number U-015630-ST
		7. Indian Allottee or Tribe Name
		8. Unit or Communitization Agreement
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		9. Well Name and Number NBU 438
2. Name of Operator El Paso Production Oil & Gas Company		10. API Well Number
3. Address of Operator P.O. Box 1148 Vernal, UT 84078	4. Telephone Number (435) 781-7023	11. Field and Pool, or Wildcat Natural Buttes
5. Location of Well Footage : 2133' FNL & 986' FWL      County : Uintah QQ, Sec, T., R., M : SWNW SEC. 33, T9S, R21E      State : UT		
12. <b>CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		

**NOTICE OF INTENT**  
 (Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input checked="" type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Approximate Date Work Will Start \_\_\_\_\_

**SUBSEQUENT REPORT**  
 (Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Date of Work Completion \_\_\_\_\_

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

\* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

OPERATOR REQUESTS TO AMEND THE CEMENT & CASING PROGRAM ORIGINALLY SUBMITTED IN THE APD (APPLICATION FOR PERMIT TO DRILL), AND PLACE THE SUBJECT WELL ON CONFIDENTIAL STATUS.

REFER TO THE ATTACHED DRILLING PROGRAM.

**RECEIVED**  
**JAN 21 2003**  
 DIV. OF OIL, GAS & MINING


14. I hereby certify that the foregoing is true and correct.

 Name & Signature Cheryl Cameron Title Operations Date 01/16/03

(State Use Only)

## DRILLING PROGRAM FOR APD

COMPANY NAME El Paso Production Company DATE January 16, 2003  
WELL NAME NBU 438 TD 8,600' MD/TVD  
FIELD Natural Buttes COUNTY Uintah STATE Utah ELEVATION 4,955' KB  
SURFACE LOCATION 2133' FNL, 986' FWL, SWNW, SEC. 33, T9S, R21E BHL Straight Hole  
OBJECTIVE ZONE(S) Wasatch, Mesa Verde  
ADDITIONAL INFO Regulatory Agencies: UDOGM, Tri-County Health Dept.



**el paso** | Production  
**DRILLING PROGRAM**

**CASING PROGRAM**

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-20'				2270	1370	254000
SURFACE	9-5/8"	0-250'	32.30	H-40	STC	16.19	11.71	4.37
						5350	4960	162000
PRODUCTION	4-1/2"	0-TD	11.60	J-55	LTC	1.76	1.23	1.08

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)  
 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)  
 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)  
 (Burst Assumptions: FG @ 9-5/8" shoe = 13.0 ppg, Max Pore Pressure = 9.0 ppg EMW)  
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 50000 lbs overpull)

**CEMENT PROGRAM**

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE		250	Class G + 2% CaCl <sub>2</sub> + 0.25 pps celloflake	140	35%	15.80	1.16
PRODUCTION	LEAD	4,300'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	460	60%	11.00	3.38
	TAIL	4,300'	50/50 Poz/G + 10% salt + 2% gel	1200	60%	14.30	1.31

**FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

**ADDITIONAL INFORMATION**

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys on bit trips. Maximum allowable hole angle is 5 degrees.

Prepared by: C. Cameron

DRILLING ENGINEER:

\_\_\_\_\_  
Dan Lindsey

DATE: \_\_\_\_\_

NBU 438  
SWNW Sec. 33, T9S, R21E  
Uintah County, UT  
U-015630-ST

**EL PASO PRODUCTION COMPANY**  
**DRILLING PROGRAM**

1. **Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
KB	4965'
Wasatch	4800'
Mesaverde	7740'
Total Depth	8600'

2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Wasatch	4800'
Gas	Mesaverde	7740'
Water	N/A	
Other Minerals	N/A	

3. **Pressure Control Equipment** (Schematic Attached)

The BOP stack will consist of one 11" 3,000 psi annular BOP, one 11" 3,000 psi double ram, and one 11' drilling spool. The lower ram will contain pipe rams, and the upper ram will contain blind rams.

The choke and kill lines and the choke manifold will have a 3,000 psi minimum pressure rating.

The hydrill will be tested to 1,500 psi. The rams, choke manifold, kelly safety valves, drill string safety valves, and inside BOP will be tested to 3,000 psi.

4. **Proposed Casing Program:** *See Sundry dated 1/16/23*

<u>Purpose</u>	<u>Depth</u>	<u>Hole Size</u>	<u>Casing Size</u>	<u>Wt/ft</u>	<u>Grade</u>	<u>Type</u>
Surface	0-250'	11" or 12 1/4"	8 5/8" or 9 5/8"	24#, 32.3#, 36#, or 40#	K-55, H-40, or J-55	ST&C
Production	0-TD	7 7/8"	4 1/2" or 5 1/2"	11.6#	N-80	LT&C

The proposed casing and cementing program shall be conducted as approved to protect and/or isolate all usable water zones potentially productive zones, lost circulation zones, abnormally pressured zones, and any prospectively valuable deposits of minerals. Any isolating medium other than cement shall receive approval prior to use. The casing setting depth shall be calculated to position the casing seat opposite a competent formation that will contain the maximum pressure to which it will be exposed during normal drilling operations. Determination of casing setting depth shall be based on all relevant factors, including: presence/absence of hydrocarbons, fracture gradients, usable water zones, formation pressures, lost circulation zones, other minerals, or other unusual characteristics.

All casing, except conductor casing, shall be new or reconditioned and tested. Used casing shall meet or exceed API standards for new casing.

The surface casing shall be cemented back to surface either during the primary cement job or by remedial cementing. If drive pipe is used, it may be left in place if its total length is less than twenty feet below the surface. If the total length of the drive pipe is equal to or greater than twenty feet, it will be pulled prior to cementing surface casing, or it will be cemented in place.

As a minimum, usable water zones shall be isolated and/or protected by having a cement top for the production casing at least 200 feet above the base of the usable water. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

Top plugs shall be used to reduce contamination of cement by displacement fluid. A bottom plug or other acceptable technique, such as a suitable preflush fluid, inner string cement method, etc., shall be utilized to help isolate the cement from contamination by the mud being displaced ahead of the cement slurry.

Maximum anticipated bottom hole pressure calculated @ 8600 TD approximately equals 3440 psi (calculated at 0.4 psi/foot).

Maximum anticipated surface pressure equals approximately 1548 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

All casing strings below the conductor shall be pressure tested to 0.22 psi/foot of casing string length or to 1500 psi, whichever is greater, but not to exceed 70% of the minimum internal yield. If pressure declines more than 10% in 30 minutes, corrective action shall be taken.

Casing design is subject to revision based on geologic conditions encountered.

**Proposed Cementing Program:** *See summary dated 1/16/03*

<u>Surface</u>	<u>Fill</u>	<u>Type &amp; Amount</u>
0-250'	250'	A minimum of 85 sx Class "G" + 2% CaCl <sub>2</sub> , 15.6 ppg, 1.19 cf/sx (Cement will be circulated to surface, about 25% excess)

<u>Production</u>	<u>Type &amp; Amount</u>
200' above the top-most resource interval	Lead: Extended, Lite, or Hi-Fill cement + additives, 11 or 12 ppg, 2.69 cf/sx
TD-500' above productive internal	Tail: Extended Class "G" or 50:50 Poz + additives, 14 ppg, or RFC, 14.0 – 14.5 ppg, 1.57 cf/sx.

For production casing, actual cement volumes will be determined from the calculated hole volume + 60% excess, minimum. Cement volumes will include an amount sufficient to circulate to surface, if possible. Operator will continue to attempt to circulate cement to surface, but at a minimum, circulation will be 200' above the top of the Green River Formation, or as directed by the Authorized Officer (AO) or Acting, or as specified in the Conditions of Approval (COA) in the Application for Permit to Drill (APD).

For surface casing, waiting on cement time will be adequate to achieve 500 psi compressive strength at the casing shoe prior to drilling out.

Anticipated cement tops will be reported as to depth, not the expected number of sacks of cement to be used. The Division of Oil, Gas, and Mining (DOGM) Office shall be notified, with sufficient lead time, in order to have a DOGM representative on location while running all casing strings and cementing.

After cementing the surface pipe and/or any intermediate strings, but before commencing any test, The casing string shall stand cemented until the cement has reached a compressive strength of at least 500 psi at the shoe. WOC time shall be recorded in the Driller's Log.

**Auxiliary Well Control Equipment to Be Used:**

Kelly Cock

A sub with a full opening (TIW) valve having threads compatible with drill string tubulars.

5. **Drilling Fluids Program:**

**WASATCH**

<u>Interval</u>	<u>Type</u>	<u>Mud Weight</u>
0-TD	Air/Air Mist/Aerated Water/Water (as hole conditions Warrant) Displace Hole to 10 ppg brine mud, prior to logging.	8.4 ppg or less



## MESAVERDE

<u>Interval</u>	<u>Type</u>	<u>Mud Weight</u>
0-TD	Air/Air Mist/Aerated Water/Water (as hole conditions warrant) Depending on hole conditions, the hole will be displaced to either 10 ppg brine or drilling mud prior to logging. If hole conditions warrant, a mud system will be used.	8.4 ppg or less

No chromate additives will be used in the mud system prior to approval to ensure adequate protection of fresh water aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well.

### **6. Evaluation Program:**

The Evaluation Program may change at the discretion of the well site geologist with approval by The Authorized Officer.

#### **Cased Hole Logs Only**

GR/Dipole Sonic/Neutron: TD-500' above the Wasatch Formation  
(to surface at times)

Drill Stem Tests: As deemed necessary

Cores: As deemed necessary

When cement has not been circulated to surface, the cement top will be determined by Either a temperature survey or cement bond log. Should a temperature survey fail to Locate the cement top, a cement bond log shall be run.

#### **Open Hole Logs**

PEX: From TD - Surface

### **7. Abnormal Conditions:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth.

### **8. Variances:**

Operator requests approval to perform drilling operations without an automatic igniter because drilling will be performed with an air/mist medium.

9. **Other Information:**

All loading lines will be placed inside the berm surrounding the tank battery.

10. **Anticipated Starting Dates & Notification of Operations:**

Anticipated commencement date shall be upon approval of the proposed APD.

Drilling Days:                      Approximately 10 days

Completion Days:                Approximately 7 days

**NBU 438  
SWNW Sec. 33, T9S, R21E  
Uintah County, UT  
U-015630-ST**

**MULTI-POINT SURFACE USE & OPERATIONS PLAN**

**1. Existing Roads:**

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

Refer to the attached directions to the proposed location site.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

*Improvements to existing access roads shall be determined at the on-site inspection.*

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

**2. Planned Access Roads:**

Refer to Topo Map B for the location of the proposed access road.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet, *unless modified at the on-site inspection*. Appropriate water control will be installed to control erosion.

*Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities shall be determined at the on-site.*

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

**3. Location of Existing Wells Within a 1-Mile Radius**

Please refer to Topo Map C.

**4. Location of Existing & Proposed Facilities**

*The following guidelines will apply if the well is productive.*

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Carlsbad Canyon (2.5Y 6/2).

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Refer to Topo Map D for the proposed pipeline placement.

**5. Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

**6. Source of Construction Materials**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

**7. Methods of Handling Waste Materials**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids. *The need for a reserve pit liner will be determined at the on-site inspection.*

If a plastic reinforced liner is used, it will be a minimum of 12 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

*Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E.*

**8. Ancillary Facilities**

None are anticipated.

**9. Well Site Layout: (See Location Layout Diagram)**

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s). ***This section is subject to modification as a result of the on-site inspection.***

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

If it is determined that a pit liner will be used at the on-site inspection, the reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Location size may change prior to the drilling pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile (s), and surface material stockpile(s).

**10. Plans for Reclamation of the Surface:**

*Producing Location:*

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic, nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

*Dry Hole/Abandoned Location:*

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of

irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

**11. Surface Ownership:**

State of Utah  
SITLA  
675 East 500 South  
Salt Lake City, UT 84102-2818

**12. Other Information:**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey has been conducted. A copy of this report is attached.

This proposed location is not within 460 feet from the boundary of the Natural Buttes Unit, nor is it within 460 feet of any non-committed tract lying within the boundaries of the Unit.

**13. Lessee's or Operators's Representative & Certification:**

Cheryl Cameron  
Regulatory Analyst  
El Paso Production Company  
P.O. Box 1148  
Vernal, UT 84078  
(435) 781-7023

Scott Palmer  
Drilling Manager  
El Paso Production Company  
9 Greenway Plaza  
Houston, TX 77046  
(832) 676-3391


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

El Paso Production Company is considered to be the operator of the subject well. El Paso Production Company agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by El Paso Production Company, State Bond No. 400JU0705.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

  
Cheryl Cameron

11/18/02

Date



**ORIGINAL**

**CULTURAL RESOURCE INVENTORY OF  
EL PASO PRODUCTION'S SEVEN WELL  
LOCATIONS IN NATURAL BUTTES,  
UINTAH COUNTY, UTAH**

**Keith R. Montgomery**

**Prepared For:**

**Bureau of Land Management  
(Vernal Field Office)  
and  
State of Utah  
School and Institutional Trust Land Administration**

**Prepared Under Contract With:**

**El Paso Production Oil and Gas Company  
1368 South 1200 East  
Vernal, Utah 84078**

**Prepared By:**

**Montgomery Archaeological Consultants  
P.O. Box 147  
Moab, Utah 84532**

**MOAC Report No. 02-42**

**March 26, 2002**

**United States Department of Interior (FLPMA)  
Permit No. 01-UT-60122**

**State of Utah Antiquities Project (Survey)  
Permit No. U-02-MQ-0124b,s**

**RECEIVED**

**NOV 22 2002**

**DIVISION OF  
OIL, GAS AND MINING**

## INTRODUCTION

A cultural resource inventory was conducted by Montgomery Archaeological Consultants (MOAC) in March 2002 for El Paso Production Oil and Gas Company's seven proposed well locations. The proposed well locations with access and pipeline corridors are situated in the Natural Buttes area, southeast of Ouray, Utah (Figures 1, 2, and 3). The survey was implemented at the request of Mr. Carroll Estes, El Paso Production Oil and Gas Company, Vernal, Utah. The project is situated on land administered by the Bureau of Land Management (BLM), Vernal Field Office, and by the State of Utah, School and Institutional Trust Land Administration (SITLA).

The objective of the inventory was to locate, document, and evaluate any cultural resources within the project area in order to comply with Section 106 of 36 CFR 800, the National Historic Preservation Act of 1966 (as amended). Also, the inventory was implemented to attain compliance with a number of federal and state mandates, including the National Environmental and Policy Act of 1969, the Archaeological and Historic Conservation Act of 1972, the Archaeological Resources Protection Act of 1979, the American Indian Religious Freedom Act of 1978, and Utah State Antiquities Act of 1973 (amended 1990).

The fieldwork was performed on March 20, 21, and 22, 2002 by Keith R. Montgomery, (Principal Investigator). The project was initiated under the auspices of U.S.D.I. (FLPMA) Permit No. 01-UT-60122 and State of Utah Antiquities Permit (Survey) No. U-02-MQ-0124b,s issued to MOAC.

A file search was performed by Keith Montgomery at the BLM Vernal Field Office on March 5, 2002. This consultation indicated that several archaeological inventories have been completed in or near the project area. In 1979, Archaeological-Environmental Research Corporation (AERC) conducted a survey of sample areas within the Natural Buttes oil and gas field for the BLM (Hauck, et.al. 1979). The survey resulted in the discovery of 20 sites, 18 of which were prehistoric, and 10 isolated finds of artifacts. One of the sites (42UN660) occurs near proposed well location NBU #436, and consists of a prehistoric temporary camp with a variety of tools and some artifacts indicating a small historic component. None of the sites found by AERC are located immediately within the project areas. In 1981, Brigham Young University completed the Magic Circle Cottonwood Wash inventory (Thompson 1981). None of the sites documented in this study occur within the current project area. In 1981, BYU also completed an inventory for the TOSCO Corporation shale oil recovery plant and facilities (Nielson 1981). None of the sites documented are in or near the project areas. In 1991, Metcalf Archaeological Consultants (MAC) inventoried eighteen Natural Butte well locations for Coastal Oil and Gas (O'Brian, et. al. 1991). None of the cultural resources inventoried occur near or within the current project areas. Metcalf Archaeological Consultants surveyed a number of well locations for Coastal Oil & Gas Corporation in 1997 (Spath 1997), none of which are in the current project areas. In 2001 and 2002, Montgomery Archaeological Consultants inventoried




Figure 1. Inventory Area of El Paso Production Oil and Gas Company's NBU #436 Well Location. USGS 7.5' Ouray SE, Utah 1964. Scale 1:24000.




Figure 2. Inventory Area of El Paso Production Oil and Gas Company's NBU #438 and NBU #439 Well Locations. USGS 7.5' Ouray SE, Utah 1964 and Big Pack Mtn. NE, Utah 1987. Scale 1:24000.




Figure 3. Inventory Area of El Paso Production Oil and Gas Company's NBU #441, NBU #442, NBU #443 and NBU #444 Well Locations. USGS 7.5' Ouray SE, Utah 1964 and Big Pack Mtn. NE, Utah 1987. Scale 1:24000.

35 El Paso Production's well locations in the Natural Buttes area (Montgomery 2001a, 2001b, 2001c, 2001d, 2002; Montgomery and Ball 2001). No archaeological sites have been documented in the immediate project areas in any of these previous inventories.

### DESCRIPTION OF PROJECT AREA

The seven proposed El Paso Production well locations, access and pipeline corridors are situated in the Natural Buttes Field, southeast of Ouray, Utah (Table 1). The legal description is T 9S, R 21E, Sections 26, 30, 33, 34 and 35 and T 10S, R 21E, Sections 1 and 2 (USGS 7.5' Ouray SE Quadrangle; USGS 7.5' Big Pack Mtn. NE Quadrangle).

Table 1. El Paso Production's Natural Butte Seven Well Locations

Well Location Designation	Legal Location	Location at Surface	Access/Pipeline	Cultural Resources
NBU #436	T 9S, R 21E, Sec. 30	2080' FNL 2125' FEL	Access 600'	None
NBU #438	T 9S, R 21E, Sec. 33	2133' FNL 986' FWL	Access/Pipeline 1200'	None
NBU #439	T 9S, R 21E, Sec. 34	345' FNL 1687' FWL	Pipeline 300'	None
NBU #441	T 9S, R 21E, Sec. 26 and 35	612' FNL 506" FWL	Access 600'	None
NBU #442	T 9S, R 21E, Sec. 35	1964' FSL 815' FWL	Access 100' Pipeline 500'	None
NBU #443	T 9S, R 21E, Sec. 35	1679' FNL 1741" FWL	Access 900' Pipeline 50'	None
NBU #444	T 10S, R 21E, Sec. 1 and 2	704' FSL 460' FWL	Access/Pipeline 900'	None

### Environment

The study area lies within the Uinta Basin physiographic unit, a distinctly bowl-shaped geologic structure (Stokes 1986:231). The Uinta Basin ecosystem is within the Green River drainage, considered to be the northernmost extension of the Colorado Plateau. The geology is comprised of Tertiary age deposits which include Paleocene age deposits, and Eocene age fluvial and lacustrine sedimentary rocks. The Uinta Formation, which is predominate in the project area, occurs as eroded outcrops formed by fluvial deposited, stream laid interbedded sandstone and mudstone, and is known for its prolific paleontological localities. Specifically, the project area occurs on the east and west sides

of Cottonwood Wash on the valley floors which are interspersed by flat topped buttes and narrow steep-sided ridges. The area is heavily dissected and carved by ephemeral drainages. The surface geology consists of hard pan residual soil armored with shale and sandstone pebbles as well as some sand shadows. The elevation averages 5200 feet a.s.l. The project occurs within the Upper Sonoran Desert Shrub Association which includes shadscale, greasewood, mat saltbrush, snakeweed, rabbitbrush, prickly pear cactus, Indian ricegrass and non-native plants and grasses. Modern disturbances include roads, and oil/gas development.

## **SURVEY METHODOLOGY**

An intensive pedestrian survey was performed for this project which is considered 100% coverage. At each of the proposed well locations, a ten acre area centered on the center stake of the location was surveyed by the archaeologists walking parallel transects spaced no more than 30 feet apart. The access and pipeline corridors were 100 feet wide, surveyed by walking parallel transects along the staked centerline, spaced no more than 10 m (30 ft) apart. A wider corridor (150 foot) was inspected when access/pipeline routes shared a corridor. Ground visibility was considered to be good. A total of 84.23 acres was inventoried, 24.48 on BLM (Vernal Field Office) administered land and 59.75 on State of Utah SITLA land.

## **RESULTS AND RECOMMENDATIONS**

The inventory of the seven proposed El Paso Production Oil and Gas Company well locations resulted in the location of no archaeological resources. Based on the findings, a determination of "no historic properties affected" is recommended for this undertaking pursuant to Section 106, CFR 800.

## REFERENCES CITED

- Hauck, F. R., D. G. Weder, and S. Kennette  
1979 Final Report on the Natural Buttes Cultural Mitigation Study. Archaeological-Environmental Research Corporation, Salt Lake City, Utah. Project No. U-78-AF-0348b. On file at the BLM Vernal Field Office.
- Montgomery, K.R.  
2001a Cultural Resource Inventory of El Paso Production's NBU #407 and NBU #408 well locations, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-01-MQ-0455b,s. On file at the Utah Division of State History.
- 2001b Cultural Resource Inventory of El Paso Production's Natural Buttes 10 Well Locations, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-01-MQ-0532b. On file at the BLM Vernal Field Office.
- 2001c Cultural Resource Inventory of El Paso Production's Natural Buttes 11 Well Locations, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-01-MQ-0738b. On file at the BLM Vernal Field Office.
- 2001d Cultural Resource Inventory of El Paso Production's Natural Buttes 8 Well Locations, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-01-MQ-0723b. On file at the BLM Vernal Field Office.
- 2002 Cultural Resource Inventory of El Paso Production's Well Locations NBU #428, NBU #440 and CIGE #285, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-02-MQ-0108b. On file at the BLM Vernal Field Office.
- Montgomery, K.R. and Ball, S.  
2001 Cultural Resource Inventory of El Paso Production Oil and Gas Company's NBU #385 Well Location, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-01-MQ-0507s. On file at the Utah Division of State History.
- Nielson, A. S.  
1981 Cultural Resource Inventory of the TOSCO Corporation Sand Wash Project in Uintah County, Utah. Brigham Young University, Cultural Resource Service Management, Provo, UT. Project No. U-81-BC-0721b. On file at the Utah Division of State History.
- O'Brian, P.K., P.M. Lubinski, and J.M. Scott  
1991 Cultural Resources Inventory for 18 proposed Coastal Oil & Gas Well and Access Locations on State of Utah Lands, Uintah County, Utah. Metcalf Archaeological Consultants, Eagle, CO. Project No. U-91-MM-044s. On file at the Utah State Division of History.



Spath, C.  
1997

Coastal Oil and Gas Corporation's Proposed CIGE #s 203, 210, 212, 220 and NBU #272 Well Pads, Pipelines and Access, Section 34, T9S, R21E, Sections 31 and 34, T9S, R22E, Section 16, T10S, R21E, and Section 11, T10S, R22E, Uintah County, Utah. Metcalf Archaeological Consultants, Eagle, CO. Project No. U-97-MM-0120s. On file at the BLM Vernal Field Office.

Stokes, W.L.  
1986

*Geology of Utah*. Utah Museum of Natural History and Utah Geological and Mineral Survey, Salt Lake City.

Thompson, C.  
1981

Cultural Resource Inventory of the Magic Circle Cottonwood Wash Project, Uintah County, Utah. Brigham Young University, Cultural Resource Service Management, Provo, UT. Project No. U-81-BC-686. On file at the Utah Division of State History.


# EL PASO PRODUCTION OIL & GAS COMPANY

NBU #438

SECTION 33, T9S, R21E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 6.9 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTH; TURN LEFT AND PROCEED IN A NORTHERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN RIGHT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE BEGINNING OF THE PROPOSED ACCESS ROAD TO THE NBU #396 TO THE SOUTHEAST; FOLLOW ROAD FLAGS IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTH; FOLLOW ROAD FLAGS IN A SOUTHERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 45.1 MILES.



# **LEGEND:**

⊙ PROPOSED LOCATION

**EL PASO PRODUCTION OIL & GAS COMPANY**

**NBU #438**

**SECTION 33, T9S, R21E, S.L.B.&M.**

**2133' FNL 986' FWL**



**Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



**TOPOGRAPHIC**  
**MAP**

**1 9 02**  
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: P.M. REVISED: 00-00-00



# EL PASO PRODUCTION OIL & GAS COMPANY

**NBU #438**

LOCATED IN UINTAH COUNTY, UTAH  
SECTION 33, T9S, R21E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY




PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHEASTERLY



- Since 1964 -

**U** **E** **L** **S** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

**LOCATION PHOTOS**

**1** **9** **02**  
MONTH DAY YEAR

**PHOTO**


TAKEN BY: G.S.

DRAWN BY: P.M.

REVISED: 00-00-00



R  
21  
E



T9S  
T10S

**LEGEND:**

————— EXISTING ROAD  
- - - - - PROPOSED ACCESS ROAD



**Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



**EL PASO PRODUCTION OIL & GAS COMPANY**

**NBU #438**  
**SECTION 33, T9S, R21E, S.L.B.&M.**  
**2133' FNL 986' FWL**

**TOPOGRAPHIC**  
**MAP**


**1 9 02**  
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: P.M. REVISED: 00-00-00

**B**  
**TOPO**



R  
21  
E



**PROPOSED LOCATION:**  
**NBU #438**

**LEGEND:**

- |                   |                         |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS  | ○ WATER WELLS           |
| ● PRODUCING WELLS | ● ABANDONED WELLS       |
| ● SHUT IN WELLS   | ● TEMPORARILY ABANDONED |

**EL PASO PRODUCTION OIL & GAS COMPANY**

**NBU #438**  
**SECTION 33, T9S, R21E, S.L.B.&M.**  
**2133' FNL 986' FWL**



**Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813




**TOPOGRAPHIC**  
**MAP**

**1 9 02**  
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: P.M. REVISED: 00-00-00







# **LEGEND:**

- EXISTING ROAD
- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



**EL PASO PRODUCTION OIL & GAS COMPANY**

**NBU #438**  
**SECTION 33, T9S, R21E, S.L.B.&M.**  
**2133' FNL 986' FWL**

**TOPOGRAPHIC**  
**MAP**

**1 9 02**  
 MONTH DAY YEAR

**SCALE: 1" = 1000'** **DRAWN BY: P.M.** **REVISED: 00-00-00**

**D**  
**TOPO**





# EL PASO PRODUCTION OIL & GAS COMPANY

## TYPICAL CROSS SECTIONS FOR



NBU #438

SECTION 33, T9S, R21E, S.L.B.&M.

2133' FNL 986' FWL

1" = 20'  
X-Section  
Scale  
1" = 50'

DATE: 1-10-02  
Drawn By: P.M.



**FIGURE #2**



### APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,210 Cu. Yds.
Remaining Location	= 7,180 Cu. Yds.
<b>TOTAL CUT</b>	<b>= 8,390 CU.YDS.</b>
<b>FILL</b>	<b>= 5,600 CU.YDS.</b>

EXCESS MATERIAL AFTER 5% COMPACTION	= 2,500 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 2,500 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 0 Cu. Yds.

3,000 PSI

# BOP STACK



004

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 11/22/2002

API NO. ASSIGNED: 43-047-34787

WELL NAME: NBU 438OPERATOR: EL PASO PROD OIL & GAS ( N1845 )CONTACT: CHERYL CAMERONPHONE NUMBER: 435-781-7023

## PROPOSED LOCATION:

SWNW 33 090S 210E

SURFACE: 2133 FNL 0986 FWL

BOTTOM: 2133 FNL 0986 FWL

UINTAH

NATURAL BUTTES ( 630 )

LEASE TYPE: 3 - State

LEASE NUMBER: U-015630-ST

SURFACE OWNER: 3 - State

PROPOSED FORMATION: MVRD

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DRO	1/28/03
Geology		
Surface		

LATITUDE: 39.99393

LONGITUDE: 109.56203

## RECEIVED AND/OR REVIEWED:

☒ Plat  
 \_\_\_\_\_ Bond: Fed[] Ind[] Sta[3] Fee[]  
 (No. 400JU0705 )  
☒ Potash (Y/N)  
☒ Oil Shale 190-5 (B) or 190-3 or 190-13  
☒ Water Permit  
 (No. 43-8496 )  
☒ RDCC Review (Y/N)  
 (Date: \_\_\_\_\_ )  
☒ Fee Surf Agreement (Y/N)

## LOCATION AND SITING:

\_\_\_\_\_ R649-2-3.  
 Unit NATURAL BUTTES ☒  
 \_\_\_\_\_ R649-3-2. General  
 Siting: 460' From Qtr/Qtr & 920' Between Wells  
 \_\_\_\_\_ R649-3-3. Exception  
☒ Drilling Unit  
 Board Cause No: 173-14  
 Eff Date: 12-2-99  
 Siting: ~1600' fr N boundary E Unc. nm. Tract  
 \_\_\_\_\_ R649-3-11. Directional Drill

COMMENTS:

Mud Prints (12-11-02)

STIPULATIONS:

① Oil shale  
 ② STATEMENT OF BASIS



# 12-02 El Paso NBU 438

## Casing Schematic

Surface

Uinta

9-5/8"  
MW 8.3  
Frac 19.3

TOC @  
0.

TOC @  
0.  
Surface  
250. MD

w/189 washout

BOP

$$(0.052)(9)(8600) = 4025 \text{ psi}$$

$$\text{Anticipated} = 3440 \text{ psi}$$

Gas

$$(0.12)(8600) = 1032 \text{ psi}$$

$$\text{MASP} = 2993 \text{ psi}$$

4800'  
washout

3934' TOC rail

4000' ± BMSGW

w/159 washout

7740'  
Membrane

4-1/2"  
MW 9.

Production  
8600. MD

Well name:	<b>12-02 EI Paso NBU 438</b>	
Operator:	<b>El Paso Production Company</b>	Project ID:
String type:	<b>Surface</b>	<b>43-047-34787</b>
Location:	<b>Uintah County</b>	

**Design parameters:**
**Collapse**

Mud weight: 8.330 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 68 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 200 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 0 psi  
Internal gradient: 0.468 psi/ft  
Calculated BHP 117 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.  
Neutral point: 219 ft

Non-directional string.

**Re subsequent strings:**

Next setting depth: 8,600 ft  
Next mud weight: 9.000 ppg  
Next setting BHP: 4,021 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 250 ft  
Injection pressure 250 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	250	9.625	32.30	H-40	ST&C	250	250	8.876	15.8

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	108	1370	12.66	117	2270	19.42	8	254	31.46 J

Prepared by: Dustin Doucet  
Utah Dept. of Natural Resources

Phone: 801-538-5281  
FAX: 801-359-3940

Date: January 23, 2003  
Salt Lake City, Utah

ENGINEERING STIPULATIONS: Surface casing cemented to surface; Oil shale  
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.  
Collapse is based on a vertical depth of 250 ft, a mud weight of 8.33 ppg The casing is considered to be evacuated for collapse purposes.  
Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:

**12-02 El Paso NBU 438**

Operator:

**El Paso Production Company**

String type:

**Production**

Project ID:

**43-047-34787**

Location:

**Uintah County****Design parameters:****Collapse**Mud weight: 9.000 ppg  
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 185 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 368 ft

Cement top: Surface

**Burst**Max anticipated surface  
pressure: 0 psi  
Internal gradient: 0.468 psi/ft  
Calculated BHP 4,021 psi

No backup mud specified.

**Tension:**8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.

Neutral point: 7,443 ft

Run	Segment		Nominal		End	True Vert	Measured	Drift	Internal
Seq	Length	Size	Weight	Grade	Finish	Depth	Depth	Diameter	Capacity
	(ft)	(in)	(lbs/ft)			(ft)	(ft)	(in)	(ft³)
1	8600	4.5	11.60	J-55	LT&C	8600	8600	3.875	199.3

Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load	Strength	Design	Load	Strength	Design	Load	Strength	Design
	(psi)	(psi)	Factor	(psi)	(psi)	Factor	(Kips)	(Kips)	Factor
1	4021	4960	1.23	4021	5350	1.33	100	162	1.62 J

El Paso Assumes  
max 50 K lbs overpull  
this has been standard practice  
Dan Lindsey 1/27/03  
1.58 w/ buoyancy

Prepared Dustin Doucet  
by: Utah Dept. of Natural ResourcesPhone: 801-538-5281  
FAX: 801-359-3940Date: January 23, 2003  
Salt Lake City, Utah

ENGINEERING STIPULATIONS: Surface casing cemented to surface; Oil shale

Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 8600 ft, a mud weight of 9 ppg The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

**DIVISION OF OIL, GAS AND MINING  
APPLICATION FOR PERMIT TO DRILL  
STATEMENT OF BASIS**

**OPERATOR:** EL PASO PRODUCTION & GAS COMPANY  
**WELL NAME & NUMBER:** NBU 438  
**API NUMBER:** 43-047-34787  
**LOCATION:** 1/4,1/4 SW/NW Sec:33 TWP: 9S RNG:21E 986' FWL 2133' FNL

**Geology/Ground Water:**

El Paso proposes to set 250' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 4,000'. A search of Division of Water Rights records shows one water well within a 10,000 foot radius of the center of section 33 . This well is approximately .5 miles from the proposed location and is listed as a mining use well. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought to above the base of the moderately saline groundwater in order to isolate it from fresher waters uphole.

**Reviewer:** Brad Hill **Date:** 12/16/02

**Surface:**

The predrill investigation of the surface was performed on 12/11/02. Floyd Bartlett and Miles Hanberg with DWR and Ed Bonner with SITLA were invited to this investigation on 12/2/02. Mr. Hanberg was present. SITLA did not have a representative present. Mr. Hanberg did not have any concerns regarding the construction of this location or the drilling of the well. This site is on State surface. This site appears to be the best site for a location in the immediate area.

**Reviewer:** David W. Hackford **Date:** 12/13/02

**Conditions of Approval/Application for Permit to Drill:**

1. A synthetic liner with a minimum thickness of 12 mils shall be properly installed and maintained in the reserve pit.



**ON-SITE PREDRILL EVALUATION**  
**Division of Oil, Gas and Mining**

**OPERATOR:** ELPASO PRODUCTION OIL & GAS COMPANY.

**WELL NAME & NUMBER:** NBU 438

**API NUMBER:** 43-047-34787

**LEASE:** U-015630-ST **FIELD/UNIT:** NATURAL BUTTES

**LOCATION:** 1/4, 1/4 SW/NW Sec: 33 TWP: 9S RNG: 21E 986' FWL 2133' FNL

**LEGAL WELL SITING:** F SEC. LINE; F 1/4, 1/4 LINE; F ANOTHER WELL.

**GPS COORD (UTM):** 4427864N 12622761N **SURFACE OWNER:** STATE OF UTAH

**PARTICIPANTS**

DAVID W. HACKFORD (DOGM), MILES HANBERG, (DWR), CARROLL ESTES, CARROLL WILSON, (EL PASO). ROBERT KAY, (UELS).

**REGIONAL/LOCAL SETTING & TOPOGRAPHY**

SITE IS ON THE WEST POINT OF A LOW RIDGE RUNNING EAST TO WEST. THERE ARE SOME SHALLOW DRAWS HEADING NORTHWEST, WEST AND SOUTHWEST OF SITE. DRAINAGE IS TO THE SOUTHWEST. SITE IS FIVE MILES SOUTH OF THE WHITE RIVER AND 16 MILES SOUTHEAST OF OURAY, UTAH.

**SURFACE USE PLAN**

**CURRENT SURFACE USE:** WILDLIFE AND LIVESTOCK GRAZING, HUNTING.

**PROPOSED SURFACE DISTURBANCE:** LOCATION WILL BE 325' BY 230'. ACCESS ROAD WILL BE 0.3 MILES.

**LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS:** SEE ATTACHED MAP FROM GIS DATABASE.

**LOCATION OF PRODUCTION FACILITIES AND PIPELINES:** ALL PRODUCTION FACILITIES WILL BE ON LOCATION AND ADDED AFTER DRILLING WELL. PIPELINE WILL FOLLOW ACCESS ROAD.

**SOURCE OF CONSTRUCTION MATERIAL:** ALL CONSTRUCTION MATERIAL WILL BE BORROWED FROM SITE DURING CONSTRUCTION OF LOCATION.

**ANCILLARY FACILITIES:** NONE WILL BE REQUIRED.

**WASTE MANAGEMENT PLAN:**

DRILLED CUTTINGS WILL BE SETTLED INTO RESERVE PIT. LIQUIDS FROM PIT WILL BE ALLOWED TO EVAPORATE. FORMATION WATER WILL BE CONFINED TO STORAGE TANKS. SEWAGE FACILITIES, STORAGE AND DISPOSAL WILL BE HANDLED BY COMMERCIAL CONTRACTOR. TRASH WILL BE CONTAINED IN TRASH BASKETS AND HAULED TO AN APPROVED LAND FILL.

**ENVIRONMENTAL PARAMETERS**

**AFFECTED FLOODPLAINS AND/OR WETLANDS:** NONE

**FLORA/FAUNA:** SALTBRUSH, SHADSCALE, PRICKLEY PEAR, CHEATGRASS, SAGE, GRASSES: PRONGHORN, COYOTES, SONGBIRDS, RAPTORS, RODENTS, RABBITS.

SOIL TYPE AND CHARACTERISTICS: LIGHT BROWN SANDY CLAY.

EROSION/SEDIMENTATION/STABILITY: VERY LITTLE NATURAL EROSION.  
SEDIMENTATION AND STABILITY ARE NOT A PROBLEM AND LOCATION CONSTRUCTION  
SHOULDN'T CAUSE AN INCREASE IN STABILITY OR EROSION PROBLEMS.

PALEONTOLOGICAL POTENTIAL: NONE OBSERVED.

**RESERVE PIT**

CHARACTERISTICS: 140' BY 70' AND 10' DEEP.

LINER REQUIREMENTS (Site Ranking Form attached): A 12 MIL LINER WILL BE  
REQUIRED FOR RESERVE PIT.

**SURFACE RESTORATION/RECLAMATION PLAN**

AS PER SITLA.

SURFACE AGREEMENT: AS PER SITLA.

CULTURAL RESOURCES/ARCHAEOLOGY: SITE WAS INSPECTED BY MONTGOMERY  
ARCHAEOLOGICAL CONSULTANTS. A REPORT OF THIS INVESTIGATION WILL BE PLACED ON  
FILE.

**OTHER OBSERVATIONS/COMMENTS**

THIS PREDRILL INVESTIGATION WAS CONDUCTED ON A COLD, FROSTY DAY WITH TWO  
INCHES OF SNOW COVER,

**ATTACHMENTS**

PHOTOS OF THIS SITE WERE TAKEN AND PLACED ON FILE.

DAVID W. HACKFORD  
DOGM REPRESENTATIVE

12/11/02. 9:30 AM  
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score  
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>5</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>20</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>5</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>0</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>

**Final Score**      30      (Level III Sensitivity)

Sensitivity Level I = 20 or more; total containment is required.

Sensitivity Level II = 15-19; lining is discretionary.

Sensitivity Level III = below 15; no specific lining is required.





UTAH DIVISION OF WATER RIGHTS  
WATER RIGHT POINT OF DIVERSION PLOT CREATED MON, DEC 16, 2002, 11:19 AM  
PLOT SHOWS LOCATION OF 1 POINTS OF DIVERSION

PLOT OF AN AREA WITH A RADIUS OF 10000 FEET FROM A POINT  
FEET, FEET OF THE CT CORNER,  
SECTION 33 TOWNSHIP 9S RANGE 21E SL BASE AND MERIDIAN

PLOT SCALE IS APPROXIMATELY 1 INCH = 4000 FEET

N O R T H

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*

\*\*\*

\*\*\*

\*\*\*

\*\*

\*\*

\*\*\*

\*\*\*

\*\*

\*\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*

\*


\*

\*

\*

\*

0




---

UTAH DIVISION OF WATER RIGHTS  
NWPLAT POINT OF DIVERSION LOCATION PROGRAM

---

MAP CHAR	WATER RIGHT	QUANTITY CFS AND/OR	AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER	DEPTH	YEAR LOG	POINT OF DIVERSION DESCRIPTION NORTH EAST CNR SEC TWN RNG B&							
0	49 355	1.0000	.00	7	1667		N	951	E	689	SW 34	9S	21E	S
WATER USE(S): MINING				OTHER	10100 Santa Monica Blvd.							PRIORITY DATE: 07/10/1		
Tosco Corporation												Los Angeles		

---



State of Utah  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210  
PO Box 145801  
Salt Lake City, Utah 84114-5801  
(801) 538-5340 telephone  
(801) 359-3940 fax  
(801) 538-7223 TTY  
www.nr.utah.gov

Michael O. Leavitt  
Governor  
Robert L. Morgan  
Executive Director  
Lowell P. Braxton  
Division Director

January 29, 2003

El Paso Production Oil & Gas Company  
P O Box 1148  
Vernal, UT 84078

Re: Natural Buttes Unit 438 Well, 2133' FNL, 986' FWL, SW NW, Sec. 33, T. 9 South,  
R. 21 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-34787.

Sincerely,

John R. Baza  
Associate Director

er

Enclosures

cc: Uintah County Assessor  
SITLA  
Bureau of Land Management, Vernal Field Office



Operator: El Paso Production Oil & Gas Company  
Well Name & Number Natural Buttes Unit 438  
API Number: 43-047-34787  
Lease: U-015630-ST

Location: SW NW                      Sec. 33                      T. 9 South                      R. 21 East

### Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

6. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

JAN. 17. 2003 3:34PM TPORT

NO. 173 P. 2

**WESTPORT OIL AND GAS COMPANY, L.P.**

410 Seventeenth Street #2300 Denver Colorado 80202-4436  
Telephone: 303 573 5404 Fax: 303 573 5609

**February 1, 2002**

Department of the Interior  
Bureau of Land Management  
2850 Youngfield Street  
Lakewood, CO 80215-7093  
Attention: Ms. Martha Maxwell

**RE: BLM Bond CO-1203**  
**BLM Nationwide Bond 158626364**  
**Surety - Continental Casualty Company**  
**Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.**  
**Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.**  
**Assumption Rider - Westport Oil and Gas Company, L.P.**

**Dear Ms. Maxwell:**

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.  
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.  
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.  
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,  
Westport Oil and Gas Company, L.P.

Debby J. Black  
Engineer Technician

Encl:



# United States Department of the Interior **RECEIVED**

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF  
OIL, GAS AND MINING

In Reply Refer To:

3106

UTU-25566 et al

(UT-924)

FEB 21 2002

### NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas  
410 Seventeenth Street, #2300 :  
Denver Colorado 80215-7093 :

#### Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405  
UTU-20895  
UTU-25566  
UTU-43156  
UTU-49518  
UTU-49519  
UTU-49522  
UTU-49523



Robert Lopez  
Chief, Branch of  
Minerals Adjudication

cc: Moab Field Office  
Vernal Field Office  
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217  
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114  
Teresa Thompson (UT-922)  
Joe Incardine (UT-921)

# memorandum

Branch of Real Estate Services  
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to:  
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.

We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.



CC: Minerals & Mining Section of RES  
Ute Energy & Mineral Resources Department: Executive Director  
chronos



IN REPLY REFER TO:  
Real Estate Services

## United States Department of the Interior

BUREAU OF INDIAN AFFAIRS  
Washington, D.C. 20240

FEB 10 2003

Carroll A. Wilson  
Principal Landman  
Westport Oil and Gas Company, L.P.  
1368 South 1200 East  
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

A handwritten signature in black ink, reading "Perry E. Brown", is positioned below the "Sincerely," text.

**ACTING**

Director, Office of Trust Responsibilities

Enclosure



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155

IN REPLY REFER TO  
UT-922

February 27, 2003

Westport Oil and Gas Company, L.P.  
Attn: Gary D. Williamson  
1670 Broadway, Suite 2800  
Denver, Colorado 80202

Re: Natural Buttes Unit  
Uintah County, Utah

Gentlemen:

On February 27, 2003, we received an indenture dated December 17, 2002, whereby El Paso Production Oil & Gas Company resigned as Unit Operator and Westport Oil and Gas Company, L.P., was designated as Successor Unit Operator for the Natural Buttes Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective February 27, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Natural Buttes Unit Agreement.

Your nationwide (Colorado) oil and gas bond No. 1203 will be used to cover all operations within the Natural Buttes Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks  
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)  
SITLA  
Division of Oil, Gas & Mining  
Minerals Adjudication Group  
File - Natural Buttes Unit (w/enclosure)  
Agr. Sec. Chron  
Fluid Chron

UT922:TAThompson:tt:02/27/2003

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 9 Greenway Plaza City Houston STATE TX ZIP 77064-0995		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: COUNTY: QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH		8. WELL NAME and NUMBER: Exhibit "A"
PHONE NUMBER: (832) 676-5933		9. API NUMBER:
		10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND # \_\_\_\_\_

State Surety Bond No. RLB0005236  
Fee Bond No. RLB0005238


EL PASO PRODUCTION OIL & GAS COMPANY

By:   
Jon R. Nelsen, Attorney-in-Fact

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.		TITLE Agent and Attorney-in-Fact	
NAME (PLEASE PRINT) David R. Dix			
SIGNATURE 		DATE 12/17/02	

(This space for State use only)



Form 3160-5  
(August 1999)UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

## SUNDRY NOTICES AND REPORTS ON WELLS

*Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.*FORM APPROVED  
OMB No. 1004-0135  
Expires November 30, 2000

5. Lease Serial No.

SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

SEE ATTACHED EXHIBIT "A"

9. API Well No.

SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UT

**SUBMIT IN TRIPLICATE - Other instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL &amp; GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED EXHIBIT "A"

## 12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	SUCCESSOR OF
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompletes horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zone. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed when testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF, BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Date

March 4, 2003

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

## OPERATOR CHANGE WORKSHEET

006

## ROUTING

1. GLH
2. CDW ✓
3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: 12-17-02

<b>FROM: (Old Operator):</b>	<b>TO: (New Operator):</b>
EL PASO PRODUCTION OIL & GAS COMPANY	WESTPORT OIL & GAS COMPANY LP
Address: 9 GREENWAY PLAZA	Address: P O BOX 1148
HOUSTON, TX 77064-0995	VERNAL, UT 84078
Phone: 1-(832)-676-5933	Phone: 1-(435)-781-7023
Account No. N1845	Account No. N2115

CA No.

Unit:

NATURAL BUTTES

## WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 377	31-09S-21E	43-047-34363	99999	FEDERAL	GW	APD
NBU 378	31-09S-21E	43-047-34364	2900	FEDERAL	GW	P
NBU 409	32-09S-21E	43-047-34421	99999	STATE	GW	APD
NBU 411	32-09S-21E	43-047-34422	99999	STATE	GW	APD
NBU 424-32E	32-09S-21E	43-047-33699	2900	STATE	GW	P
NBU 27	33-09S-21E	43-047-30304	2900	STATE	GW	PA
NBU 27-A	33-09S-21E	43-047-30398	2900	STATE	GW	PA
NBU 262	33-09S-21E	43-047-32929	2900	FEDERAL	GW	S
NBU 396	33-09S-21E	43-047-34480	2900	FEDERAL	GW	DRL
NBU 428	33-09S-21E	43-047-34709	99999	STATE	GW	APD
NBU 438	33-09S-21E	43-047-34787	99999	STATE	GW	APD
NBU CIGE 56-34-9-21	34-09S-21E	43-047-30530	2900	STATE	GW	P
NBU CIGE 87D-34-9-21	34-09S-21E	43-047-30869	2900	STATE	GW	P
NBU 98V	34-09S-21E	43-047-31327	2900	FEDERAL	GW	TA
CIGE 114-34-9-21	34-09S-21E	43-047-31915	2900	FEDERAL	GW	S
CIGE 143-34-9-21	34-09S-21E	43-047-31995	2900	FEDERAL	GW	P
NBU 221	34-09S-21E	43-047-32499	2900	FEDERAL	GW	PA
NBU 221X	34-09S-21E	43-047-32545	2900	STATE	GW	P
CIGE 236-34-9-21	34-09S-21E	43-047-32861	2900	STATE	GW	P
CIGE 203-34-9-21	34-09S-21E	43-047-32881	2900	STATE	GW	P

## OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
5. If **NO**, the operator was contacted on: \_\_\_\_\_

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

1. Changes entered in the Oil and Gas Database on: 03/18/2003
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 03/18/2003
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

**STATE WELL(S) BOND VERIFICATION:**

1. State well(s) covered by Bond Number: RLB 0005236

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: 158626364

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: RLB 0005239

**FEE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB 0005238
2. The **FORMER** operator has requested a release of liability from their bond on: N/A  
The Division sent response by letter on: N/A

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

**COMMENTS:**

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0135  
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

007

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Multiple Wells - see attached

5. Lease Serial No.

Multiple Wells - see attached

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

891008900A

8. Well Name and No.

Multiple Wells - see attached

9. API Well No.

Multiple Wells - see attached

10. Field and Pool, or Exploratory Area

Natural Buttes Unit

11. County or Parish, State

Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☐ Other

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Westport Oil & Gas requests a variance to Onshore Order No. 4, Part IIIC.a. requiring each sales tank be equipped with a pressure-vacuum thief hatch and/or vent line valve. The variance is requested as an economic analysis shows the value of the shrunk condensate will not payout the incremental cost of purchasing and maintaining the valve resulting in a loss of value over the producing life of the well.

The volume lost to shrinkage by dropping the tank pressure from 6 ozs. to 0 psig is shown to be 0.3% of the tank volume. This was determined by lab analysis of a representative sample from the field. The sample shrunk from 98.82% of original volume to 98.52% when the pressure was dropped. The average NBU well produces approximately 6 bbls condensate per month. The resulting shrinkage would amount to 0.56 bbls per month lost volume due to shrinkage. The value of the shrunk and lost condensate does not recoup or payout the cost of installing and maintaining the valves and other devices that hold the positive tank pressure. An economic run based on the loss and costs is attached. Westport Oil & gas requests approval of this variance in order to increase the value of the well to the operator and the mineral royalty owners.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

J.T. Conley

Signature

COPY SENT TO OPERATOR

Date:

Initials:

Title

Date

Operations Manager

9-2-2003

SEP 10 2003

DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Office

Date:

Accepted by the  
Utah Division of  
Oil, Gas and Mining

Federal Approval of This  
Action Is Necessary

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

# Westport Oil & Gas, L.P.

## Project Economics Worksheet

### Instructions:

Fill in blue boxed areas with before and after project data. The evaluation results are shown below and graphed automatically at the bottom of the page. This sheet is protected to prevent accidental alteration of the formulas. See JTC for changes. OPX entered as annual costs and/or as unit OPX costs for \$/BF and \$/MCF

Project Name:

Condensate Shrinkage Economics

Is this job a well pull or production rig job ??? ☐ N (Y or N)

	BEFORE \$/Year	AFTER \$/Year	DIFFERENCE \$/Year
Gross Oil Revenue	\$1,088	\$1,099	\$11
Gross Gas Revenue	\$0	\$0	\$0
NGL Revenue	\$0	\$0	\$0
PULING UNIT SERVICE			\$0
WIRELINE SERVICE			\$0
SUBSURF EQUIP REPAIRS			\$0
COMPANY LABOR			\$0
CONTRACT LABOR	\$0	\$200	\$200
CONTR SERVICE			\$0
LEASE FUEL GAS	\$0	\$0	\$0
UTILITIES - ELECTRICITY	\$0	\$0	\$0
CHEMICAL TREATING			\$0
MATERIAL & SUPPLY	\$0	\$150	\$150
WATER & HAULING			\$0
ADMINISTRATIVE COSTS			\$0
GAS PLANT PROCESSING			\$0
Totals	\$0	\$350	\$350

Increased OPX Per Year

### Investment Breakdown:

	Cap/Exp Code	Cost, \$
Capital \$	820/830/840	\$1,200
Expense \$	830/860	\$0
Total \$		\$1,200

Oil Price	\$ 23.00	\$/BO
Gas Price	\$ 3.10	\$/MCF
Electric Cost	\$ -	\$/ HP / day
OPX/BF	\$ 2.00	\$/BF
OPX/MCF	\$ 0.62	\$/MCF

### Production & OPX Detail:

	Before		After		Difference
Oil Production	0.192	BOPD	0.194	BOPD	0.002
Gas Production	0	MCFPD	0	MCFPD	0
Wtr Production	0	BWPD	0	BWPD	0
Horse Power		HP		HP	0
Fuel Gas Burned		MCFPD		MCFPD	0

### Project Life:

Life = 20.0 Years  
(Life no longer than 20 years)

### Internal Rate of Return:

After Tax IROR = #DIV/0!

### AT Cum Cashflow:

Operating Cashflow = (\$2,917) (Discounted @ 10%)

### Gross Reserves:

Oil Reserves = 6 BO  
Gas Reserves = 0 MCF  
Gas Equiv Reserves = 38 MCFE

### Payout Calculation:

$$\text{Payout} = \frac{\text{Total Investment}}{\text{Sum(OPX + Incremental Revenue)}} = 1$$


Payout occurs when total AT cashflow equals investment  
See graph below, note years when cashflow reaches zero

Payout = NEVER Years or #VALUE! Days

### Notes/Assumptions:

An average NBU well produces 0.192 Bopd with no tank pressure. The production is increased to 0.194 Bopd if 4 ozs of pressure are placed on the tank. The increased production does not payout the valve cost or the estimated annual maintenance costs.

Project: Condensate Shrinkage Economics



# Westport Oil and Gas, Inc.

NBU/Ouray Field

RFL 2003-022

## COMPARISON OF FLASH BACK PRESSURES

Calculated by Characterized Equation-of-State

Flash Conditions		Gas/Oil Ratio (scf/STbbl) (A)	Specific Gravity of Flashed Gas (Air=1.000)	Separator Volume Factor (B)	Separator Volume Percent (C)
psig	°F				

### Calculated at Laboratory Flash Conditions

80	70			1.019	
0	122	30.4	0.993	1.033	101.37%
0	60	0.0	—	1.000	98.14%

### Calculated Flash with Backpressure using Tuned EOS

80	70			1.015	
6.0 oz	65	24.6	0.777	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
4.0 oz	65	24.7	0.778	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
2.0 oz	65	24.7	0.779	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
0	65	24.8	0.780	1.003	98.82%
0	60	0.0	—	1.000	98.52%

(A) Cubic Feet of gas at 14.696 psia and 60 °F per Barrel of Stock Tank Oil at 60 °F.

(B) Barrels of oil at indicated pressure and temperature per Barrel of Stock Tank Oil at 60 °F.

(C) Oil volume at indicated pressure and temperature as a percentage of original saturated oil volume.

Note: Bubblepoint of sample in original sample container was 80 psig at 70° F with 1 cc water

WELL	LEGALS	STFLEASENO	CANUMBER	APINO
NBU 419	21-10-21 NWNE	U02278	891008900A	430473437600S1
NBU 420	20-10-21 SESE	UTU02278	891008900A	430473437700S1
NBU 421	20-10-21 NESE	UTU02278	891008900A	430473437800S1
NBU 422	29-10-22 SWSE	UTU469	891008900A	430473441400S1
NBU 423	29-10-22 NWSE	UTU469	891008900A	430473441500S1
NBU 424	29-10-22 NESW	UTU0145824	891008900A	430473441600S1
NBU 425	11-10-21 SENE	UTU01190	891008900A	430473441000S1
NBU 426	11-10-21 SWNE	UTU01190	891008900A	430473441100S1
NBU 427	11-10-21 NWNE	UTU01190	891008900A	430473441800S1
NBU 428	33-9-21 NWSW	UTU015630ST	891008900A	430473470900S1
NBU 434	14-10-21 SENE	UTU465	891008900A	430473448100S1 ✓
NBU 435	28-9-21 NWNW	UTU0576	891008900A	430473480500S1
NBU 436	30-9-21 SWNE	UTU0581	891008900A	430473478000S1
NBU 438	33-9-21 SWNW	UTU015630-ST	891008900A	430473478700S1
NBU 439	34-9-21 NENW	UTU01194-A-ST	891008900A	430473478600S1 ✓
NBU 440	34-9-21 SWNW	UTU01194-A-ST	891008900A	430473478500S1
NBU 441	35-9-21 NWNW	UTU01194-A-ST	891008900A	430473479100S1
NBU 442	35-9-21 NWSW	UTU01194-A-ST	891008900A	430473478800S1
NBU 443	35-9-21 SENW	UTU01194-ST	891008900A	430473478900S1
NBU 444	1-10-21 SWSW	UTU02842B	891008900A	430473479600S1
NBU 445	30-9-21 NWSE	UTU0581	891008900A	430473486700S1
NBU 446	8-9-21 SENW	UTU0149767	891008900A	430473462100S1 ✓
NBU 448	22-9-20 NWSW	UTU0577B	891008900A	430473478200S1
NBU 452	8-9-21 SWNE	UTU0149767	891008900A	430473487500S1
NBU 453	8-9-21 NWSE	UTU0575B	891008900A	430473481600S1
NBU 454	28-9-21 NWSE	UTU0576	891008900A	430473469800S1 ✓
NBU 455	29-9-21 SWSE	UTU0581	891008900A	430473469900S1 ✓
NBU 456	22-9-21 SESW	UTU010950A	891008900A	430473481800S1
NBU 457	22-9-21 NESE	UTU010950A	891008900A	430473481700S1
NBU 458	23-9-21 SENW	UTU0149075	891008900A	430473481900S1
NBU 459	27-9-21 NESE	UTU01194A-ST	891008900A	430473468000S1 ✓
NBU 460	30-9-21 SENE	UTU0581	891008900A	430473469700S1 ✓
NBU 461	14-10-22 SWNE	U01197A-ST	891008900A	430473482300S1
NBU 462	15-10-22 SENW	U-01196-A	891008900A	430473483900S1 ✓
NBU 463	15-10-22 NWNE	UTU025187	891008900A	430473484000S1
NBU 464	15-10-22 NENW	U025187	891008900A	430473484600S1
NBU 465	29-10-22 NWSW	SL070220A	891008900A	430473486000S1 ✓
NBU 466	32-10-22 NWNE	ML22798	891008900A	430473482400S1 ✓
NBU 468	11-10-21 SENW	UTU0149080	891008900A	430473485600S1
NBU 470	7-10-22 SWSE	UTU466	891008900A	430473483300S1
NBU 471	17-10-22 NWNE	UTU01196E	891008900A	430473483400S1
NBU 472	32-10-22 SWNE	ML22798	891008900A	430473489600S1 ✓
NBU 492-7E	7-9-21 LOT 1	UTU0149767	891008900A	430473421700S1
NBU 922-36I	36-9-22 NESE	MS22650	891008900A	430473510700S1 ✓
UTE TRAIL 083X	9-10-22 SENE	UTU01196D	891008900A	430471538800S1
UTE TRAIL 088X	2-10-21 SESE	ML13826	891008900A	430471538900S1 ✓

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

009

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

U-015630-ST

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

NATURAL BUTTES UNIT

8. WELL NAME and NUMBER:

NBU 438

9. API NUMBER:

4304734787

10. FIELD AND POOL, OR WILDCAT:

NATURAL BUTTES

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☒

OTHER

2. NAME OF OPERATOR:

WESTPORT OIL & GAS COMPANY L.P.

3. ADDRESS OF OPERATOR:

1368 S. 1200 E.

CITY VERNAL

STATE UT

ZIP 84078

PHONE NUMBER:

(435) 781-7024

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2133'FNL & 986'FWL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☒ NOTICE OF INTENT  
(Submit in Duplicate)

Approximate date work will start:

☐ SUBSEQUENT REPORT  
(Submit Original Form Only)

Date of work completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☒ OTHER: APD EXTENSION

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR REQUESTS AUTHORIZATION FOR AN ONE YEAR EXTENSION, SO THAT THE DRILLING OPERATIONS MAY BE COMPLETED.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date:

01-25-05

By:

COPY SENT TO OPERATOR

Date:

1-25-05

Initials:

CHD

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 1/12/2005

(This space for State use only)

RECEIVED  
JAN 19 2005  
DIV. OF OIL, GAS & MINING



**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 4304734787  
**Well Name:** NBU 438  
**Location:** SWNW SECTION 33-T9S-R21E  
**Company Permit Issued to:** WESTPORT OIL & GAS CO., L.P.  
**Date Original Permit Issued:** 1/29/2003

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

  
Signature

1/12/2003

Date

Title: REGULATORY ANALYST

Representing: WESTPORT OIL & GAS COMPANY L.P.

RECEIVED  
JAN 19 2005  
DIV. OF OIL, GAS & MINING

0.08

**STATE OF UTAH**  
**DEPARTMENT OF NATURAL RESOURCES**  
**DIVISION OF OIL, GAS AND MINING**

**CONFIDENTIAL**

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b> Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT – for such proposals		6. Lease Designation and Serial Number U-015630-ST
		7. Indian Allottee or Tribe Name
		8. Unit or Communitization Agreement NATURAL BUTTES UNIT
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		9. Well Name and Number NBU #438
2. Name of Operator WESTPORT OIL & GAS COMPANY L.P.		10. API Well Number 43-047-34787
3. Address of Operator 1368 SOUTH 1200 EAST VERNAL, UT 84078	4. Telephone Number (435) 781-7024	11. Field and Pool, or Wildcat NATURAL BUTTES
5. Location of Well Footage : 2133'FNL & 986'FWL      County : UINTAH QQ, Sec, T., R., M : SWNW SECTION 33-T9S-R21E      State : UTAH		
12. <b>CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		

<p align="center"><b>NOTICE OF INTENT</b> (Submit in Duplicate)</p> <table style="width:100%;"> <tr> <td><input type="checkbox"/> Abandonment</td> <td><input type="checkbox"/> New Construction</td> </tr> <tr> <td><input type="checkbox"/> Casing Repair</td> <td><input type="checkbox"/> Pull or Alter Casing</td> </tr> <tr> <td><input type="checkbox"/> Change of Plans</td> <td><input type="checkbox"/> Recompletion</td> </tr> <tr> <td><input type="checkbox"/> Conversion to Injection</td> <td><input type="checkbox"/> Shoot or Acidize</td> </tr> <tr> <td><input type="checkbox"/> Fracture Treat</td> <td><input type="checkbox"/> Vent or Flare</td> </tr> <tr> <td><input type="checkbox"/> Multiple Completion</td> <td><input type="checkbox"/> Water Shut-Off</td> </tr> <tr> <td colspan="2"><input checked="" type="checkbox"/> Other <u>ONE YEAR EXTENSION</u></td> </tr> </table> <p>Approximate Date Work Will Start <u>IMMEDIATE</u></p>	<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing	<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion	<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare	<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off	<input checked="" type="checkbox"/> Other <u>ONE YEAR EXTENSION</u>		<p align="center"><b>SUBSEQUENT REPORT</b> (Submit Original Form Only)</p> <table style="width:100%;"> <tr> <td><input type="checkbox"/> Abandonment *</td> <td><input type="checkbox"/> New Construction</td> </tr> <tr> <td><input type="checkbox"/> Casing Repair</td> <td><input type="checkbox"/> Pull or Alter Casing</td> </tr> <tr> <td><input type="checkbox"/> Change of Plans</td> <td><input type="checkbox"/> Shoot or Acidize</td> </tr> <tr> <td><input type="checkbox"/> Conversion to Injection</td> <td><input type="checkbox"/> Vent or Flare</td> </tr> <tr> <td><input type="checkbox"/> Fracture Treat</td> <td><input type="checkbox"/> Water Shut-Off</td> </tr> <tr> <td colspan="2"><input type="checkbox"/> Other _____</td> </tr> </table> <p>Date of Work Completion _____</p> <p><small>Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.        * Must be accompanied by a cement verification report.</small></p>	<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing	<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize	<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> Other _____	
<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction																										
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing																										
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion																										
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize																										
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare																										
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off																										
<input checked="" type="checkbox"/> Other <u>ONE YEAR EXTENSION</u>																											
<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction																										
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing																										
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize																										
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare																										
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off																										
<input type="checkbox"/> Other _____																											

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

THE OPERATOR REQUESTS AUTHORIZATION FOR AN ONE YEAR EXTENSION FOR THE SUBJECT WELL LOCATION, SO THAT DRILLING OPERATIONS MAY BE COMPLETED.

**Approved by the  
 Utah Division of  
 Oil, Gas and Mining**

Date: 01-22-04By: [Signature]

COPY SENT TO OPERATOR

Date: 1-23-04Initials: CHD

14. I hereby certify that the foregoing is true and correct.

Name &amp; Signature

Sheila Upcheg

Title

Regulatory Analyst

Date

01/12/04

(State Use Only)

**RECEIVED**  
**JAN 20 2004**  
 DIV. OF OIL, GAS & MINING

**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 43-047-34787  
**Well Name:** NBU #438  
**Location:** SWNW SECTION 33-T9S-R21E  
**Company Permit Issued to:** WESTPORT OIL & GAS CO., L.P.  
**Date Original Permit Issued:** 1/29/03

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

  
Signature

1/12/2004

Date

Title: REGULATORY ANALYST

Representing: WESTPORT OIL & GAS COMPANY L.P.

OPERATOR WESTPORT O&G COMPANY L.P.  
ADDRESS 1368 SOUTH 1200 EAST  
VERNAL, UTAH 84078

OPERATOR ACCT. NO. N 2115

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	14522	43-047-34421	STATE 921-32L	NWSW	32	9S	21E	UINTAH	1/19/2005	1/25/05

WELL 1 COMMENTS:  
MIRU PETE MARTIN BUCKET RIG  
SPUD WELL LOCATION ON 1/19/05 AT 8:00 AM.  
WSTC uncommitted

CONFIDENTIAL

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	14523	43-047-34872	STATE 921-32M	SWSW	32	9S	21E	UINTAH	1/19/2005	1/25/05

WELL 2 COMMENTS:  
MIRU PETE MARTIN BUCKET RIG.  
SPUD WELL LOCATION ON 1/19/05 AT 9:00 AM.  
WSTC uncommitted

CONFIDENTIAL

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	2900	43-047-34787	NBU 438	SWNW	33	9S	21E	UINTAH	1/19/2005	1/25/05

WELL 3 COMMENTS:  
MIRU PETE MARTIN BUCKET RIG.  
SPUD WELL LOCATION ON 1/13/05 AT 1300 HRS.  
MVRD (WSPUD - NBU 438) CO

CONFIDENTIAL

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	14524	43-047-35745	BONANZA 1023-1E	SWNW	1	10S	23E	UINTAH	1/20/2005	1/25/05

WELL 4 COMMENTS:  
MIRU PETE MARTIN BUCKET RIG.  
SPUD WELL LOCATION ON 1/20/05 AT 8 AM.  
MVRD

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	14525	43-047-34741	OURAY 6-225	NESW	6	9S	21E	UINTAH	1/17/2005	1/25/05

WELL 5 COMMENTS:  
MIRU PETE MARTIN BUCKET RIG  
SPUD WELL LOCATION ON 1/7/05 AT 8 AM.  
WSTC

CONFIDENTIAL

ACTION CODES (See instructions on back of form)  
A - Establish new entity for new well (single well only)  
B - Add new well to existing entity (group or unit well)  
C - Re-assign well from one existing entity to another exist  
D - Re-assign well from one existing entity to a new entity  
E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.  
(3/89)

Post-It* Fax Note 7671		Date	# of pages
To	ERLENE Russell	From	Shana Upchendo
Co./Dept.	UT DORM	Co.	WESTPORT O&G AS CO
Phone	(801) 328-5330	Phone	(435) 781-7024
Fax #	(801) 328-3940	Fax #	(435) 781-7094

Signature: Shana Upchendo

REGULATORY ANALYST 01/24/05  
Title Date

Phone No. (435) 781-7024

RECEIVED  
JAN 24 2005

DIV. OF OIL, GAS & MINING

011

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: U-015630-ST
2. NAME OF OPERATOR: WESTPORT OIL & GAS COMPANY L.P.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NATURAL BUTTES UNIT
3. ADDRESS OF OPERATOR: 1368 S. 1200 E. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2133'FNL & 986'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E		8. WELL NAME and NUMBER: NBU 438
PHONE NUMBER: (435) 781-7024		9. API NUMBER: 4304734787
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 1/19/2005	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: WELL SPUD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" CONDUCTOR PIPE. CMT W/28 SX READY MIX CMT.

SPUD WELL LOCATION ON 1/19/05 AT 1300 HRS.

RECEIVED  
FEB 01 2005  
DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 1/24/2005

(This space for State use only)

012

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: U-015630-ST
2. NAME OF OPERATOR: WESTPORT OIL & GAS COMPANY L.P.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 S. 1200 E. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2133'FNL & 986'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E		8. WELL NAME and NUMBER: NBU 438
PHONE NUMBER: (435) 781-7024		9. API NUMBER: 4304734787
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 2/3/2005	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: DRILLING OPERATIONS
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU BILL MARTIN AIR RIG. DRILLED 12 1/4" SURFACE HOLE TO 2560'. RAN 9 5/8" 32.3# H-40 SURFACE CSG. LEAD CMT W/220 SX HIFILL CLASS G @11.0 PPG 3.82 YIELD TAILED W/225 PREM GLASS G @15.8 PPG 1.15 YIELD. TOP OUT W/225 SX PREM CLASS G @15.8 PPG 1.15 YIELD. HOLE STAYED FULL.

WORT.

**RECEIVED**

**FEB 0 / 2005**

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) <u>SHEILA UPCHEGO</u>	TITLE <u>REGULATORY ANALYST</u>
SIGNATURE <u><i>Sheila Upchego</i></u>	DATE <u>2/4/2005</u>

(This space for State use only)

**STATE OF UTAH**  
**DEPARTMENT OF NATURAL RESOURCES**  
**DIVISION OF OIL, GAS AND MINING**

013

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.  
 Use APPLICATION FOR PERMIT -- for such proposals

## 1. Type of Well

☐ Oil Well      ☒ Gas Well      ☐ Other (specify)

## 2. Name of Operator

WESTPORT OIL &amp; GAS COMPANY, L.P.

## 3. Address of Operator

1368 SOUTH 1200 EAST, VERNAL, UT 84078

## 4. Telephone Number

435-781-7044

## 5. Location of Well

Footage : 2133' FNL, 986' FWL

County : UINTAH

QQ, Sec, T., R., M : SWNW, SECTION 33, T9S, R21E

State : UTAH

## 6. Lease Designation and Serial Number

U-015630-ST

## 7. Indian Allottee or Tribe Name

## 8. Unit or Communitization Agreement

NATURAL BUTTES

## 9. Well Name and Number

NBU 438

## 10. API Well Number

43-047-34787

## 11. Field and Pool, or Wildcat

NATURAL BUTTES

## 12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

**NOTICE OF INTENT**

(Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Other <u>TD CHANGE</u>	

Approximate Date Work Will Start ASAP**SUBSEQUENT REPORT**

(Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Date of Work Completion \_\_\_\_\_

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

\* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

WESTPORT OIL & GAS COMPANY, L.P. HAS NEED TO CHANGE THE ORIGINALLY PERMITTED TD OF 8600' TO 9650' TO REACH THE DESIRED FORMATION.

**Approved by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
 Date 04-14-05  
 By: [Signature]

**RECEIVED****APR 08 2005**

DIV. OF OIL, GAS &amp; MINING

COPIES SENT TO OPERATOR

NO: 4-15-04  
 BY: CHD

14. I hereby certify that the foregoing is true and correct.

Name & Signature RALEEN WEDDLE Title REGULATORY Date 04/06/05

(State Use Only)



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
WESTPORT OIL & GAS COMPANY L.P.

3. ADDRESS OF OPERATOR:  
1368 S. 1200 E. CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-7024

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2133'FNL & 986'FWL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: FINAL DRILLING OPERATIONS
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

FINISHED DRILLING FROM 2560'. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. LEAD CMT W/802 SX PREM LITE II @12.0 PPG 2.37 YIELD. TAILED W/1377 SX 50/50 POZ @14.3 PPG 1.31 YIELD.

RELEASED CAZA 12 ON 4/10/05 AT 1200 HRS.

RECEIVED

APR 13 2005

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 4/11/2005

(This space for State use only)

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: U-015630-ST
2. NAME OF OPERATOR: WESTPORT OIL & GAS COMPANY L.P.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NATURAL BUTTES UNIT
3. ADDRESS OF OPERATOR: 1368 S. 1200 E. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2133'FNL & 986'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E		8. WELL NAME and NUMBER: NBU 438
PHONE NUMBER: (435) 781-7024		9. API NUMBER: 4304734787
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 4/30/2005	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: PRODUCTION START-UP
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 4/30/05 AT 10:00 AM.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

RECEIVED  
MAY 10 2005  
DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 5/3/2005

(This space for State use only)

**WESTPORT OIL & GAS COMPANY, LP**

**CHRONOLOGICAL HISTORY**

**NBU 438**

UINTAH COUNTY, UT

	SPUD	Surface Casing	Activity	Status
12/15/04			Build Location, 15% complete	Caza 12
12/16/04			Build Location, 15% complete	Caza 12
12/17/04			Build Location, 15% complete	Caza 12
12/20/04			Build Location, 25% complete	Caza 12
12/21/04			Build Location, 30% complete	Caza 12
12/22/04			Build Location, 35% complete	Caza 12
12/23/04			Build Location, 40% complete	Caza 12
12/27/04			Build Location, 40% complete	Caza 12
12/28/04			Build Location, 65% complete	Caza 12
12/29/04			Build Location, 65% complete	Caza 12
12/30/04			Build Location, 80% complete	Caza 12
12/31/04			Build Location, 80% complete	Caza 12
01/03/05			Build Location, 80% complete	Caza 12
01/04/05			Build Location, 90% complete	Caza 12
01/05/05			Build Location, 90% complete	Caza 12
01/06/05			Location built, WOBR	Caza 12
01/07/05			Location built, WOBR	Caza 12
01/10/05			Location built, WOBR	Caza 12
01/11/05			Location built, WOBR	Caza 12
01/12/05			Location built, WOBR	Caza 12
01/13/05			Location built, WOBR	Caza 12

01/14/05			Location built, WOB	Caza 12
01/17/05			Location built, WOB	Caza 12
01/18/05			Location built, WOB	Caza 12
01/19/05			Location built, WOB	Caza 12
01/20/05			Location built, WOB	Caza 12
01/21/05			Location built, WOB	Caza 12
01/24/05			Location built, WOB	Caza 12
01/25/05			Location built, WOB	Caza 12
01/26/05			Location built, WOB	Caza 12
01/27/05			Location built, WOB	Caza 12
01/28/05			Location built, WOB	Caza 12
01/31/05	1/29/04	14" @ 40'	MIAR. Drill to 1630'. DA	Caza 12
02/01/05	1/29/04	9 5/8" @ 2520'	Drill to 2560'. Set csg.	Caza 12
02/02/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/03/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/04/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/07/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/08/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/09/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/10/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/11/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/14/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/15/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/16/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/17/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/18/05	1/29/04	9 5/8" @ 2520'		Caza 12
02/21/05	1/29/04	9 5/8" @ 2520'		Caza 12

02/22/05	1/29/04	9 5/8" @ 2520'	Caza 12
02/23/05	1/29/04	9 5/8" @ 2520'	Caza 12
02/24/05	1/29/04	9 5/8" @ 2520'	Caza 12
02/25/05	1/29/04	9 5/8" @ 2520'	Caza 12
02/28/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/01/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/02/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/03/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/04/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/07/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/08/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/09/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/10/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/11/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/14/05	1/29/04	9 5/8" @ 2520'	Caza 12
03/15/05	1/29/04	9 5/8" @ 2520'	WORT Caza 12
03/16/05	1/29/04	9 5/8" @ 2520'	WORT Caza 12
03/17/05	1/29/04	9 5/8" @ 2520'	WORT Caza 12
03/18/05	1/29/04	9 5/8" @ 2520'	WORT Caza 12
03/21/05	TD: 2560' Csg. 9 5/8"@ 2523' MW: 8.4 SD: 3/X/05 DSS: 0 Finish MIRU. Test BOPE. PU DP and BHA. Drill cmt and FE @ report time.		
03/22/05	TD: 3660' Csg. 9 5/8"@ 2523' MW: 8.4 SD: 3/21/05 DSS: 1 Drill cement and FE. Rotary spud 7 7/8" hole @ 1030 hrs 3/21/05. Drill from 2560'-3660'. DA @ report time.		
03/23/05	TD: 4565' Csg. 9 5/8"@ 2523' MW: 8.5 SD: 3/21/05 DSS: 2 Drill from 3660'-4565'. DA @ report time.		
03/24/05	TD: 5125' Csg. 9 5/8"@ 2523' MW: 9.0 SD: 3/21/05 DSS: 3 Drill from 4565'-5125'. DA @ report time.		
03/25/05	TD: 5560' Csg. 9 5/8"@ 2523' MW: 9.2 SD: 3/21/05 DSS: 4 Drill from 5125'-5560'. DA @ report time.		
03/28/05	TD: 6710' Csg. 9 5/8"@ 2523' MW: 10.1 SD: 3/21/05 DSS: 7		

**Drill from 5560'-6710'. DA @ report time.**

<b>03/29/05</b>	<b>TD: 6835' Csg. 9 5/8"@ 2523' MW: 10.6 SD: 3/21/05 DSS: 8</b> <b>Drill from 6710'-6774'. TFNB and MM. Drill from 6774'-6835'. DA @ report time.</b>
<b>03/30/05</b>	<b>TD: 6835' Csg. 9 5/8"@ 2523' MW: 10.6 SD: 3/21/05 DSS: 8</b> <b>Drill from 6710'-6774'. TFNB and MM. Drill from 6774'-6835'. DA @ report time.</b>
<b>03/31/05</b>	<b>TD: 7740' Csg. 9 5/8"@ 2523' MW: 11.4 SD: 3/21/05 DSS: 10</b> <b>Drill from 7325'-7740'. DA @ report time.</b>
<b>04/01/05</b>	<b>TD: 7944' Csg. 9 5/8"@ 2523' MW: 11.4 SD: 3/21/05 DSS: 11</b> <b>Drill from 7740'-7944'. DA @ report time.</b>
<b>04/04/05</b>	<b>TD: 8445' Csg. 9 5/8"@ 2523' MW: 11.7 SD: 3/21/05 DSS: 14</b> <b>Drill from 7944'-8221'. TFNB &amp; MM. Drill from 8221'-8445'. DA @ report time.</b>
<b>04/05/05</b>	<b>TD: 8650' Csg. 9 5/8"@ 2523' MW: 11.7 SD: 3/21/05 DSS: 15</b> <b>Drill from 8445'-8618'. Shut well in and circulate out gas. Drill to 8650'. DA @ report time.</b>
<b>04/06/05</b>	<b>TD: 8842' Csg. 9 5/8"@ 2523' MW: 12.5 SD: 3/21/05 DSS: 16</b> <b>Drill from 8650'-8842'. DA @ report time.</b>
<b>04/07/05</b>	<b>TD: 9180' Csg. 9 5/8"@ 2523' MW: 12.5 SD: 3/21/05 DSS: 17</b> <b>Drill from 8842'-9180'. DA @ report time.</b>
<b>04/08/05</b>	<b>TD: 9465' Csg. 9 5/8"@ 2523' MW: 12.7 SD: 3/21/05 DSS: 18</b> <b>Drill from 9180'-9465'. DA @ report time.</b>
<b>04/11/05</b>	<b>TD: 9478' Csg. 9 5/8"@ 2523' MW: 12.7 SD: 3/21/05 DSS: 21</b> <b>Drill from 9465'-9478' TD. Circulate bottoms up and short trip to 8000'. CCH and POOH for logs. Run Triple Combo. TIH and CCH for casing. POOH laying down drill string. Run and cement 4 1/2" Production Casing. ND BOPE and set slips. Release rig @ 1200 hrs 4/10/05. Rig down rotary tools. Will move to the NBU 442 this am.</b>
<b>04/21/05</b>	<b>PROG: RD OFF STATE 921-32L ROAD RIG TO NBU 438 SPOT IN EQUIP, RU NU BOP TEST CSG &amp; BOP TO 7500#, GOOD TEST, SDFN.</b>
<b>04/22/05</b>	<b>PROG: TALLY &amp; PU 2-3/8 J-55 TBG TAG @ 9430', REV BTM UP POOH SDFN.</b>
<b>04/25/05</b>	<b>PROG: MIRU CUTTERS, RIH W/CBL-CCL LOG F/9394'-2200' PU 3-3/8 PERF GUNS LOADED W/23 GM .35 HOLES 4 SPF PERF @ 9284'-90' 9200'-10' NO BLOW, RD CUTTERS, PREP TO FRAC, SWI SDFWE.</b>
<b>04/26/05</b>	<b>PROG: RU SCHLUM &amp; CUTTERS.</b>  <b>STAGE 1#: PERFS 9200-10' , 9284-90'. OPEN PRES 1675. BROKE @ 3730, INJ R 6.2, INJ P: 3700, ISIP: 3580, FG: .85. MP: 6524, MR: 47.3, AP: 5175, AR: 44.3, FG: .81, ISIP 3500, NPI: - 80, CLEAN 2668 BBLs, SD 341,500#.</b>  <b>STAGE 2#: RIH SET CBP @ 8695, PERF 8586-90, 8668-70, AFTER PERF 1525# BROKE @ 3671, INJ R 6.1, INJ P: 3050, ISIP: 2450, FG: .72, MP: 5579, MR: 36.8, AP: 4447, AR: 34.6, FG: .81, ISIP: 3220, NPI: 770, CLEAN 884, SD 103,000#.</b>  <b>STAGE 3#: RIH SET CBP @ 8480, PERF 8352-58, 8446-52', AFTER PERF 2090#, BROKE @</b>

2840, INJ R: 6.1, INJ P: 2620, ISIP: 2350, FG: .72, MP: 5794, MR: 45, AP: 4616, AR: 43.6, FG: .82, ISIP: 3250, NPI: 900, CLEAN 2059 BBLs, SD 272,000#.

STAGE 4#: RIH SET CBP @ 8205', PERF 7900-04, 8169-75. SWI 6:30 PM.

**04/27/05** PROG: BRK PERF @ 7900'-8175' @ 2730#, INJ RT: 41.1 BPM, INJ PSI: 5460#, ISIP: 2450#, FG: .74. FRAC W/90700# 20/40 SD & 701 BBL YF120ST+ GEL FLUID, MP: 4922#, MR: 42.7 BPM, AP: 4507#, AR: 39.2 BPM, ISIP: 3114#, FG: .82, NPI: 664#.

STAGE #5: RIH SET 5K CBP @ 7750' PERF @ 7714'-20' 4 SPF BRK PERF @ 2310#. INJ RT: 36.6 BPM, INJ PSI: 4231#, ISIP: 1915#, FG: .69, FRAC W/127500# 20/40 SD & 981 BBL YF120ST+ FLUID, MP: 4271#, MR: 36.9 BPM, AP: 3420#, AR: 35.6 BPM, ISIP: 2690#, FG: .78, NPI: 775#. RIH SET 5K CBP @ 7600'. RD SCHLUMBERGER & CUTTERS. RU FLOOR, RIH W/3-7/8 BIT POBS ON 2-3/8 TBG TAG @ 7600'. RU DRLG EQUIP, DRL OUT 5K CBP. RIH 1000# KICK. RIH TAG @ 7720' 30' SD ON PLUG DRL OUT SD & CBP @ 7750'. RIH TAG @ 8170' 30' SD ON PLUG DRL OUT SD & CBP @ 8200' 900# KICK. RIH TAG @ 8440' 40' SD DRL OUT SD & CBP @ 8480' 400# KICK. FLW WL CLEAN SWI SDFN.

**04/28/05** PROG: SICP: 2200#, RIH TAG @ 9025' 25' SD ON PLUG DRL OUT SD & CBP @ 9050' 400# KICK CLEAN OUT TO PB 125' SD. FLW WL CLEAN. POOH LD 27 JTS 2-3/8 LAND TBG W/263 JTS ON WL HEAD, ND BOP, NU TREE, PMP OFF BIT, RD TRUN WL TO FLWBACK CREW.

WELL ON FLOWBACK, FLOWBACK REPORT: CP: 2200#, TP: 2140#, 20/64 CHK, 31 BWPH, 24 HRS, SD: TRACE, TTL BBLs FLWD: 4026, TODAY'S LTR: 7,293 BBLs, LOAD REC TODAY: 4,026 BBLs, REMAINING LTR: 3,267 BBLs, TOTAL LOAD REC TO DATE: 4,026#.

**04/29/05** PROG: WELL ON FLOWBACK, FLOWBACK REPORT: CP: 2200#, TP: 2300#, 20/64 CHK, 25 BWPH, 24 HRS, SD: TRACE, TTL BBLs FLWD: 726, TODAY'S LTR: 3,267 BBLs, LOAD REC TODAY: 726 BBLs, REMAINING LTR: 2,541 BBLs, TOTAL LOAD REC TO DATE: 4,752 BBLs.

**05/02/05** **ON SALES**  
04/30/05: 1210 MCF, 0 BC, 360 BW, TP: 2412#, CP: 2643#, 18/64 CHK, 20 HRS, LP: 140#.

**05/03/05** **ON SALES**  
05/01/05: 2261 MCF, 0 BC, 480 BW, TP: 2361#, CP: 3215#, 16/64 CHK, 24 HRS, LP: 135#.



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: U-015630-ST
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR: WESTPORT OIL & GAS COMPANY L.P.		7. UNIT or CA AGREEMENT NAME NATURAL BUTTES UNIT
3. ADDRESS OF OPERATOR: 1368 S. 1200 E. CITY VERNAL STATE UT ZIP 84078		8. WELL NAME and NUMBER: NBU 438
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2133'FNL & 986'FWL  AT TOP PRODUCING INTERVAL REPORTED BELOW:  AT TOTAL DEPTH:		9. API NUMBER: 4304734787
10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E
12. COUNTY UINTAH		13. STATE UTAH

14. DATE SPUDDED: 1/19/2005	15. DATE T.D. REACHED: 4/11/2005	16. DATE COMPLETED: 4/30/2005	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 4955'GL
18. TOTAL DEPTH: MD 9,478 TVD	19. PLUG BACK T.D.: MD 9,430 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) ✓ CBL-CCL-GR, HRT/MICROLOG SD/PSN,			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	54#		40		28			
12 1/4"	9 5/8 H-40	32.3#		2,560		670			
7 7/8	4 1/2 I-80	11.6#		9,478		2179			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	8,492							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) MESAVERDE	7,714	9,210			7,714 9,210	0.35		Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
7714'-9210'	PMP 7523 BBLs YF120ST & 934,700# 20/40 SD

29. ENCLOSED ATTACHMENTS:

- |   |  |                                       |   |
|---|--|---------------------------------------|---|
| <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS                         | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT   | <input type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS   | <input type="checkbox"/> OTHER: _____ |   |

30. WELL STATUS:

PROD

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in Item #26)

DATE FIRST PRODUCED: 4/30/2005		TEST DATE: 5/1/2005		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,261		WATER – BBL: 480		PROD. METHOD: FLOWING							
CHOKE SIZE: 16/64		TBG. PRESS. 2,361		CSG. PRESS. 3,215		API GRAVITY		BTU – GAS		GAS/OIL RATIO		24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,261		WATER – BBL: 480		INTERVAL STATUS: PROD	

## INTERVAL B (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL C (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL D (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
WASATCH MESAVARDE	4,886 7,670	7,670			

## 35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 5/27/2005

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

Division of Oil, Gas and Mining  
**OPERATOR CHANGE WORKSHEET**

ROUTING
1. DJJ
2. CDW

**X Change of Operator (Well Sold)**

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

**1/6/2006**

<b>FROM:</b> (Old Operator): N2115-Westport Oil & Gas Co., LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024	<b>TO:</b> ( New Operator): N2995-Kerr-McGee Oil & Gas Onshore, LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024
---	--

CA No.		Unit:		NATURAL BUTTES UNIT				
WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- If **NO**, the operator was contacted on: \_\_\_\_\_
- (R649-9-2) Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a 3 LA wells & all PA wells transferred
- Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
- Federal and Indian Units:**  
The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
- Federal and Indian Communization Agreements ("CA"):**  
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, Transfer of Authority to **Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: \_\_\_\_\_

**DATA ENTRY:**

- Changes entered in the **Oil and Gas Database** on: 5/15/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
- Bond information entered in RBDMS on: 5/15/2006
- Fee/State wells attached to bond in RBDMS on: 5/16/2006
- Injection Projects to new operator in RBDMS on: \_\_\_\_\_
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

**BOND VERIFICATION:**

- Federal well(s) covered by Bond Number: CO1203
- Indian well(s) covered by Bond Number: RLB0005239
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG  
The Division sent response by letter on: \_\_\_\_\_

**LEASE INTEREST OWNER NOTIFICATION:**

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

**COMMENTS:**

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED  
OMB No. 1004-0135  
Expires November 30, 2000

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006.

KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

BLM BOND = C01203

BIA BOND = RLB0005237

APPROVED 5/16/06

Earlene Russell

Division of Oil, Gas and Mining  
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RANDY BAYNE

Title

DRILLING MANAGER

Signature

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**

**Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.**

FORM APPROVED  
OMB No. 1004-0135  
Expires November 30, 2000

5. Lease Serial No.

**MULTIPLE LEASES**

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

**MUTIPLE WELLS**

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

**UINTAH COUNTY, UTAH**

**SUBMIT IN TRIPLICATE - Other instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

**WESTPORT OIL & GAS COMPANY L.P.**

3a. Address

**1368 SOUTH 1200 EAST VERNAL, UT 84078**

3b. Phone No. (include area code)

**(435) 781-7024**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**SEE ATTACHED**

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <b>CHANGE OF OPERATOR</b>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

**APPROVED 5/16/06**

*Earlene Russell*  
Division of Oil, Gas and Mining  
Earlene Russell, Engineering Technician

**RECEIVED**

**MAY 10 2006**

**DIV. OF OIL, GAS & MINING**

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

**BRAD LANEY**

Title

**ENGINEERING SPECIALIST**

Signature

Date

**May 9, 2006**

**THIS SPACE FOR FEDERAL OR STATE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: U-015630-ST
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2133'FNL, 986'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E		8. WELL NAME and NUMBER: NBU 438
		9. API NUMBER: 4304734787
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input checked="" type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


THE OPERATOR REQUESTS AUTHORIZATION TO RECOMPLETE THE SUBJECT WELL LOCATION. THE OPERATOR PROPOSES TO COMPLETE THE WASATCH INTERVALS, AND COMMINGLE THE NEWLY WASATCH INTERVALS WITH THE EXISTING MESAVERDE INTERVALS.

PLEASE REFER TO THE ATTACHED RECOMPLETION PROCEDURE.

COPY SENT TO OPERATOR

Date: 7.16.2008

Initials: KS

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE 	DATE 7/9/2008

(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE: 7/15/08

BY: [Signature] (See Instructions on Reverse Side)

Cause 173-14

RECEIVED

JUL 11 2008

DIV. OF OIL, GAS & MINING

**Name:** NBU 438  
**Location:** SW NW Sec 33 T9S R21E  
**Uintah County, UT**  
**Date:** 06/10/2008

**ELEVATIONS:** 4955 GL 4970 KB

**TOTAL DEPTH:** 9478 **PBTD:** 9430  
**SURFACE CASING:** 9 5/8", 36# J-55 ST&C @ 2523'  
**PRODUCTION CASING:** 4 1/2", 11.6#, I-80 LT&C @ 9477'  
 Marker Joint **4547'**

**TUBULAR PROPERTIES:**

	BURST (psi)	COLLAPSE (psi)	DRIFT DIA. (in.)	CAPACITIES	
				(bbl/ft)	(gal/ft)
2 3/8" 4.7# J-55 tbg	7,700	8,100	1.901"	0.00387	0.1624
4 1/2" 11.6# I-80 (See above)	7780	6350	3.875"	0.0155	0.6528
2 3/8" by 4 1/2" Annulus				0.0101	0.4227

**TOPS:**

1550' Green River  
 2280' Mahogany  
 4805' Wasatch  
 7670' Mesaverde

**GENERAL:**

- A minimum of **31** tanks (cleaned lined 500 bbl) of recycled water will be required. Note: Use biocide in tanks and the water needs to be at least 45°F at pump time.
- All perforation depths are from Halliburtons Induction-Density-Neutron log dated 04/08/2005
- **7** fracturing stages required for coverage.
- Procedure calls for 8 CBP's (**8000** psi).
- Calculate open perforations after each breakdown. If less than 60% of the perforations appear to be open, ball out with 15% HCl.
- Put scale inhibitor 3 gals/1000 gals (in pad and 1/2 the ramp) and 10 gals/1000 gals in all flushes except the final stage. Remember to pre-load the casing with scale inhibitor for the very first stage with 10 gpt.
- 30/50 mesh Ottawa sand, **Slickwater frac.**
- Maximum surface pressure **6200** psi.
- Flush volumes are the sum of slick water and acid used during displacement (include scale inhibitor as mentioned above). **DO NOT OVERDISPLACE.** Stage acid and scale inhibitor if necessary to cover the next perforated interval.
- Service companies need to provide surface/production annulus pop-offs to be set for 1500 psi for each frac.



- Pump **resin coated sand** last 5,000# of all frac stages
- Tubing Currently Landed @~8490
- Originally completed on 04/26/2005

**Existing Perforations:**

Zone	Top Perf	Bottom Perf	SPF	Holes
MESAVERDE	7714	7720	4	24
MESAVERDE	7900	7904	2	8
MESAVERDE	8169	8175	4	24
MESAVERDE	8352	8358	4	24
MESAVERDE	8446	8452	4	24
MESAVERDE	8586	8590	4	16
MESAVERDE	8668	8670	2	4
MESAVERDE	9200	9210	4	40
MESAVERDE	9284	9290	4	24

**PROCEDURE:**

1. MIRU. Control well with recycled water and biocide as required. ND WH, NU BOP's and test.
2. TOO H with 2-3/8", 4.7#, J-55 tubing (currently landed at ~8490'). Visually inspect for scale and consider replacing if needed.
3. If tbg looks ok consider running a gauge ring to 7350 (50' below proposed CBP). Otherwise P/U a mill and C/O to 7350 (50' below proposed CBP).
4. Set 8000 psi CBP at ~ 7300'. Pressure test BOP and casing to 6000 psi. .
5. Perf the following with 3-3/8" gun, 23 gm, 0.36"hole:
 

Zone	From	To	spf	# of shots
WASATCH	7080	7090	3	30
WASATCH	7098	7102	3	12
6. Breakdown perfs and establish injection rate (include scale inhibitor in fluid). Fracture as outlined in Stage 1 on attached listing. Under-displace to ~7030' and trickle 250gal 15%HCL w/ scale inhibitor in flush .
7. Set 8000 psi CBP at ~6970'. Perf the following 3-3/8" gun, 23 gm, 0.36"hole:
 

Zone	From	To	spf	# of shots
WASATCH	6864	6867	2	6
WASATCH	6930	6940	4	40

8. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 2 on attached listing. Under-displace to ~6814' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

9. Set 8000 psi CBP at ~6747'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6601	6603	4	8
WASATCH	6624	6628	4	16
WASATCH	6715	6717	4	8

10. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 3 on attached listing. Under-displace to ~6551' trickle 250gal 15%HCL w/ scale inhibitor in flush.

11. Set 8000 psi CBP at ~6316'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6109	6111	4	8
WASATCH	6209	6213	4	16
WASATCH	6282	6286	4	16

12. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 4 on attached listing. Under-displace to ~6059' and trickle 250gal 15%HCL w/ scale inhibitor in flush.  
NOTE TIGHT SPACING

13. Set 8000 psi CBP at ~6020'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	5977	5990	3	39

14. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 5 on attached listing. Under-displace to ~5927' and trickle 250gal 15%HCL w/ scale inhibitor in flush.  
NOTE TIGHT SPACING

15. Set 8000 psi CBP at ~5916'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	5776	5780	3	12
WASATCH	5810	5816	4	24
WASATCH	5884	5886	3	6

16. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 6 on attached listing. Under-displace to ~5726' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

17. Set 8000 psi CBP at ~5591'. Perf the following 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	5407	5409	4	8
WASATCH	5550	5554	4	16
WASATCH	5559	5561	4	8

18. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 7 on attached listing. Under-displace to ~5357' and flush only with recycled water.

19. Set 8000 psi CBP at ~5357'.

20. TIH with 3 7/8" bit, pump off sub, SN and tubing.

21. Drill plugs and clean out to PBTD. Shear off bit and land tubing at  $\pm 6834'$  unless indicated otherwise by the well's behavior. This well will be commingled.

22. RDMO

**For design questions, please call**  
**Curtis Caile, Denver, CO**  
**(406)-490-2742 (Cell)**  
**(720)-929-6194 (Office)**

**For field implementation questions, please call**  
**Robert Miller, Vernal, UT**  
**4350781 7041 (Office)**

NOTES:

The sand from 7300-7400' is wet and will be avoided.

4234.7664  
100.827771

100-622771																			
Stage	Zone	Feet of Pay	Perfs		SPF	Holes	Rate BPM	Fluid Type	Initial ppg	Final ppg	Fluid	Volume BBLs	Cum Vol BBLs	Fluid % of frac	Sand % of frac	Sand lbs	Cum. Sand lbs	Footage from CBP to Flush	Scale Inhib., gal.
			Top, ft.	Bot, ft.															
1	WASATCH	1	7080	7090	3	30	Varied	Pump-in test			Slickwater	0	0						
	WASATCH	1	7098	7102	3	12	0	ISIP and 5 min ISIP											45
	WASATCH	1		No Perfs		50		Slickwater Pad			Slickwater	177	177	15.0%	0.0%	0	0		22
	WASATCH	13		No Perfs		50		Slickwater Ramp	0.25	1.25	Slickwater	589	766	50.0%	39.7%	18,563	18,563		37
	WASATCH	1		No Perfs		50		Slickwater Ramp	1.25	2	Slickwater	413	1,179	35.0%	60.3%	28,153	46,716		0
	WASATCH	1		No Perfs		50		Flush (4-1/2")				109	1,288				46,716		45
	WASATCH	1		No Perfs				ISDP and 5 min ISDP											150
		22	# of Perfs/stage			42						Flush depth				gal/ft CBP depth	2,250 6,970	2,123 lbs sand/ft	60
2	WASATCH	1	6964	6967	2	6	26.8	<< Above pump time (min)			Slickwater	0	0						
	WASATCH	1	6930	6940	4	40	Varied	Pump-in test											
	WASATCH	1		No Perfs		50		ISIP and 5 min ISIP											
	WASATCH	1		No Perfs		50		Slickwater Pad			Slickwater	397	397	15.0%	0.0%	0	0		50
	WASATCH	1		No Perfs		50		Slickwater Ramp	0.25	1.25	Slickwater	1,324	1,722	50.0%	39.7%	41,719	41,719		83
	WASATCH	1		No Perfs		50		Slickwater Ramp	1.25	2	Slickwater	927	2,649	35.0%	60.3%	63,273	104,992		0
	WASATCH	1		No Perfs		50		Flush (4-1/2")				106	2,755				104,992		44
	WASATCH	2		No Perfs				ISDP and 5 min ISDP											177
		45	# of Perfs/stage			46						Flush depth				gal/ft CBP depth	2,500 6,747	2,359 lbs sand/ft	67
3	WASATCH	1	6601	6603	4	8	57.5	<< Above pump time (min)			Slickwater	0	0						
	WASATCH	1	6624	6628	4	16	Varied	Pump-in test											
	WASATCH	1	6715	6717	4	8	0	ISIP and 5 min ISIP											
	WASATCH	1		No Perfs		50		Slickwater Pad			Slickwater	221	221	15.0%	0.0%	0	0		28
	WASATCH	2		No Perfs		50		Slickwater Ramp	0.25	1.25	Slickwater	737	958	50.0%	39.7%	23,203	23,203		46
	WASATCH	1		No Perfs		50		Slickwater Ramp	1.25	2	Slickwater	516	1,473	35.0%	60.3%	35,191	58,395		0
	WASATCH	2		No Perfs		50		Flush (4-1/2")				102	1,575				58,395		41
		28	# of Perfs/stage			32						Flush depth				gal/ft CBP depth	2,250 6,316	2,123 lbs sand/ft	235
4	WASATCH	1	6109	6111	4	8	32.8	<< Above pump time (min)			Slickwater	0	0						
	WASATCH	2	6209	6213	4	16	Varied	Pump-in test											
	WASATCH	1	6282	6286	4	16	0	ISIP and 5 min ISIP											
	WASATCH	3		No Perfs		50		Slickwater Pad			Slickwater	285	285	15.0%	0.0%	0	0		36
	WASATCH	3		No Perfs		50		Slickwater Ramp	0.25	1.25	Slickwater	951	1,236	50.0%	39.7%	29,953	29,953		60
	WASATCH	4		No Perfs		50		Slickwater Ramp	1.25	2	Slickwater	666	1,902	35.0%	60.3%	45,429	75,382		0
	WASATCH	3		No Perfs		50		Flush (4-1/2")				94	1,996				75,382		39
	WASATCH	1		No Perfs				ISDP and 5 min ISDP											135
		36	# of Perfs/stage			40						Flush depth				gal/ft CBP depth	2,250 6,020	2,123 lbs sand/ft	39
5	WASATCH	2	5977	5990	3	39	41.8	<< Above pump time (min)			Slickwater	0	0						
	WASATCH	1		No Perfs		50	Varied	Pump-in test											
	WASATCH	1		No Perfs		50		ISIP and 5 min ISIP											
	WASATCH	2		No Perfs		50		Slickwater Pad			Slickwater	299	299	15.0%	0.0%	0	0		38
	WASATCH	2		No Perfs		50		Slickwater Ramp	0.25	1.25	Slickwater	997	1,296	50.0%	39.7%	31,406	31,406		63
	WASATCH	2		No Perfs		50		Slickwater Ramp	1.25	2	Slickwater	698	1,994	35.0%	60.3%	47,633	79,039		0
	WASATCH	2		No Perfs		50		Flush (4-1/2")				92	2,086				79,039		38
	WASATCH	1		No Perfs				ISDP and 5 min ISDP											139
		34	# of Perfs/stage			39						Flush depth				gal/ft CBP depth	2,500 5,916	2,359 lbs sand/ft	11
6	WASATCH	9	5776	5780	3	12	43.5	<< Above pump time (min)			Slickwater	0	0						
	WASATCH	4	5910	5916	4	24	Varied	Pump-in test											
	WASATCH	10	5984	5986	3	6	0	ISIP and 5 min ISIP											
	WASATCH	9		No Perfs		50		Slickwater Pad			Slickwater	464	464	15.0%	0.0%	0	0		59
	WASATCH	1		No Perfs		50		Slickwater Ramp	0.25	1.25	Slickwater	1,548	2,012	50.0%	39.7%	46,750	48,750		98
	WASATCH	1		No Perfs		50		Slickwater Ramp	1.25	2	Slickwater	1,083	3,095	35.0%	60.3%	73,938	122,688		0
	WASATCH	1		No Perfs		50		Flush (4-1/2")				89	3,184				122,688		36
	WASATCH	1		No Perfs				ISDP and 5 min ISDP											192
		52	# of Perfs/stage			42						Flush depth				gal/ft CBP depth	2,500 5,691	2,359 lbs sand/ft	135
7	WASATCH	1	5407	5409	4	8	66.5	<< Above pump time (min)			Slickwater	0	0						
	WASATCH	1	5550	5554	4	16	Varied	Pump-in test											
	WASATCH	1	5569	5561	4	8	0	ISIP and 5 min ISIP											
	WASATCH	1		No Perfs		50		Slickwater Pad			Slickwater	75	75	15.0%	0.0%	0	0		9
	WASATCH	1		No Perfs		50		Slickwater Ramp	0.25	1.25	Slickwater	250	325	50.0%	39.7%	7,875	7,875		16
	WASATCH	1		No Perfs		50		Slickwater Ramp	1.25	2	Slickwater	175	500	35.0%	60.3%	11,944	19,819		0
	WASATCH	1		No Perfs		50		Flush (4-1/2")				83	583				19,819		0
	WASATCH	1		No Perfs				ISDP and 5 min ISDP											25
		11	# of Perfs/stage			32						LOOK Flush depth				gal/ft CBP depth	2,000 5,357	1,888 lbs sand/ft	0
Totals		226				273	12.1					gals bbls	13,466	bbls		Total Sand	607,030	LOOK	
													29.9	tenics			Total Scale Inhib. -	934	

NBU 438 Recomplete  
Perforation and CBP Summary

Stage	Zones	Perforations		SPF	Holes	Fracture Coverage			
		Top, ft	Bottom, ft						
1	WASATCH	7080	7080	3	30	7028.5	to		7028.5
	WASATCH	7098	7102	3	12	7033.5	to		7033.5
	WASATCH		No Perfs			7063	to		7063.5
	WASATCH		No Perfs			7078	to		7080.5
	WASATCH		No Perfs			7092	to		7093
	WASATCH		No Perfs			7095	to		7095
	WASATCH		No Perfs			7102	to		7102.5
	WASATCH		No Perfs			7105	to		7105.5
	WASATCH		No Perfs			7129.5	to		7130.5
	WASATCH		No Perfs			7135	to		7135.5
	WASATCH		No Perfs			7150	to		7150.5
	WASATCH		No Perfs			7160	to		7160
	WASATCH		No Perfs			7162	to		7162
	# of Perfs/stage				42	CBP DEPTH 5,970			
2	WASATCH	6854	6857	2	6	6805.5	to		6805.5
	WASATCH	6930	6940	4	40	6820	to		6820
	WASATCH		No Perfs			6831.5	to		6831.5
	WASATCH		No Perfs			6835	to		6835
	WASATCH		No Perfs			6839	to		6839
	WASATCH		No Perfs			6844	to		6845
	WASATCH		No Perfs			6855.5	to		6855
	WASATCH		No Perfs			6855	to		6857.5
	WASATCH		No Perfs			6872	to		6872.5
	WASATCH		No Perfs			6884.5	to		6885.5
	WASATCH		No Perfs			6889.5	to		6889.5
	WASATCH		No Perfs			6903.5	to		6903.5
	WASATCH		No Perfs			6923.5	to		6923.5
	WASATCH		No Perfs			6929.5	to		6942
	WASATCH		No Perfs			6944	to		6948.5
	WASATCH		No Perfs			6958.5	to		6950
	WASATCH		No Perfs			6965	to		6965
	WASATCH		No Perfs			6969	to		6971
	WASATCH		No Perfs			6974.5	to		6975
	WASATCH		No Perfs			6982	to		6983
	WASATCH		No Perfs			6985.5	to		6988.5
	WASATCH		No Perfs			6984.5	to		6995
	WASATCH		No Perfs			7001.5	to		7001.5
	# of Perfs/stage				48	CBP DEPTH 5,747			
3	WASATCH	6601	6603	4	8	6588	to		6588.5
	WASATCH	6624	6628	4	16	6590	to		6590.5
	WASATCH	6715	6717	4	8	6592	to		6592.5
	WASATCH		No Perfs			6594	to		6594.5
	WASATCH		No Perfs			6603	to		6604
	WASATCH		No Perfs			6609.5	to		6610.5
	WASATCH		No Perfs			6612	to		6613.5
	WASATCH		No Perfs			6619.5	to		6619.5
	WASATCH		No Perfs			6622.5	to		6623
	WASATCH		No Perfs			6631.5	to		6631.5
	WASATCH		No Perfs			6632.5	to		6633
	WASATCH		No Perfs			6643	to		6643
	WASATCH		No Perfs			6658.5	to		6659
	WASATCH		No Perfs			6660.5	to		6660.5
	WASATCH		No Perfs			6662	to		6662.5
	WASATCH		No Perfs			6665.5	to		6665.5
	WASATCH		No Perfs			6685	to		6689
	WASATCH		No Perfs			6692.5	to		6697.5
	WASATCH		No Perfs			6703	to		6703
	WASATCH		No Perfs			6706.5	to		6706.5
	WASATCH		No Perfs			6715.5	to		6717
	WASATCH		No Perfs			6721	to		6721
	WASATCH		No Perfs			6727	to		6730.5
	# of Perfs/stage				32	CBP DEPTH 5,318			
4	WASATCH	6109	6111	4	8	6098.5	to		6099
	WASATCH	6209	6213	4	16	6091	to		6092.5
	WASATCH	6282	6285	4	16	6094	to		6094.5
	WASATCH		No Perfs			6095.5	to		6095.5
	WASATCH		No Perfs			6099	to		6103
	WASATCH		No Perfs			6109	to		6112
	WASATCH		No Perfs			6114.5	to		6114.5
	WASATCH		No Perfs			6121	to		6122
	WASATCH		No Perfs			6124	to		6124.5
	WASATCH		No Perfs			6128	to		6128
	WASATCH		No Perfs			6142.5	to		6142.5
	WASATCH		No Perfs			6155	to		6156.5
	WASATCH		No Perfs			6166.5	to		6169
	WASATCH		No Perfs			6181	to		6182
	WASATCH		No Perfs			6184	to		6185.5
	WASATCH		No Perfs			6187.5	to		6188
	WASATCH		No Perfs			6190	to		6190.5
	WASATCH		No Perfs			6200	to		6201
	WASATCH		No Perfs			6207.5	to		6208
	WASATCH		No Perfs			6216	to		6218.5
	WASATCH		No Perfs			6235.5	to		6238
	WASATCH		No Perfs			6239	to		6239.5
	WASATCH		No Perfs			6262	to		6263.5
	WASATCH		No Perfs			6264.5	to		6265.5
	WASATCH		No Perfs			6274.5	to		6274.5
	WASATCH		No Perfs			6282.5	to		6288
	WASATCH		No Perfs			6288	to		6288.5
	WASATCH		No Perfs			6290.1	to		6291
	WASATCH		No Perfs			6294	to		6294.5
	WASATCH		No Perfs			6288	to		6299
	# of Perfs/stage				40	CBP DEPTH 5,020			
5	WASATCH	5977	5980	3	39	5940.5	to		5942
	WASATCH		No Perfs			5944	to		5944
	WASATCH		No Perfs			5948.5	to		5948.5
	WASATCH		No Perfs			5950.5	to		5952
	WASATCH		No Perfs			5953.5	to		5955.5
	WASATCH		No Perfs			5960	to		5963
	WASATCH		No Perfs			5966	to		5966.5
	WASATCH		No Perfs			5973	to		5984
	WASATCH		No Perfs			6002.5	to		6003
	WASATCH		No Perfs			6005	to		6005.5
	WASATCH		No Perfs			6016.5	to		6017
	WASATCH		No Perfs			6021.5	to		6023
	# of Perfs/stage				39	CBP DEPTH 5,816			
6	WASATCH	5778	5780	3	12	5778	to		5784
	WASATCH	5810	5816	4	24	5789.5	to		5793
	WASATCH	5884	5885	3	8	5796	to		5808
	WASATCH		No Perfs			5808.5	to		5817
	WASATCH		No Perfs			5818.5	to		5819
	WASATCH		No Perfs			5821.5	to		5822.5
	WASATCH		No Perfs			5829.5	to		5830
	WASATCH		No Perfs			5831	to		5833
	WASATCH		No Perfs			5836	to		5836
	WASATCH		No Perfs			5837.5	to		5837.5
	WASATCH		No Perfs			5855	to		5855
	WASATCH		No Perfs			5877.5	to		5885.5
	WASATCH		No Perfs			5880.5	to		5884
	WASATCH		No Perfs			5872.5	to		5872.5
	WASATCH		No Perfs			5874.5	to		5875
	WASATCH		No Perfs			5876.5	to		5877
	WASATCH		No Perfs			5878.5	to		5878.5
	WASATCH		No Perfs			5879.5	to		5881.5
	WASATCH		No Perfs			5884.5	to		5885.5
	WASATCH		No Perfs			5885.5	to		5885.5
	WASATCH		No Perfs			5893	to		5895
	WASATCH		No Perfs			5898.5	to		5899
	# of Perfs/stage				42	CBP DEPTH 5,591			
7	WASATCH	5467	5469	4	8	5400.5	to		5401.5
	WASATCH	5550	5554	4	16	5407.5	to		5408.5
	WASATCH	5559	5561	4	8	5454	to		5455
	WASATCH		No Perfs			5487	to		5488
	WASATCH		No Perfs			5491.5	to		5492
	WASATCH		No Perfs			5494.5	to		5494.5
	WASATCH		No Perfs			5510.5	to		5511.5
	WASATCH		No Perfs			5531.5	to		5531.5
	WASATCH		No Perfs			5557	to		5558
	WASATCH		No Perfs			5559	to		5561
	# of Perfs/stage				32	CBP DEPTH 5,357			
Totals					273				

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
KERR MCGEE OIL & GAS ONSHORE LP

3. ADDRESS OF OPERATOR:  
1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-7024

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2133'FNL, 986'FWL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:  
U-015630-ST

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:  
UNIT #891008900A

8. WELL NAME and NUMBER:  
NBU 438

9. API NUMBER:  
4304734787

10. FIELD AND POOL, OR WILDCAT:  
NATURAL BUTTES

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: SHUT-IN
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR HAS NOT COMPLETED THE RECOMPLETION FOR THE SUBJECT WELL LOCATION AS ORIGINALLY PLANNED. WHILE ON PREPARING TO RECOMLETE THE SUBJECT WELL LOCATION. THE OPERATOR FOUND A CASING LEAK AT APPROXIMATELY 1776'-1798'. THE OPERATOR NOTIFIED DUSTIN DOUCET WITH THE DIVISION OF OIL, GAS AND MINING DEPARTMENT AND GOT A VERBAL APPROVAL TO REPAIR THE CASING LEAK. THE OPERATOR HAS REPAIRED THE CASING LEAK.

AT THIS TIME THE OPERATOR WILL NOT COMMENCE THE RECOMPLETION AS PLANNED. THE OPERATOR REQUESTS TO RESCIND THE APPROVED RECOMPLETION. DUE TO WELL CASING NOT BEING ABLE TO HOLD OUT FOR A RECOMPLETION. THE OPERATOR IS CURRENTLY EVALUATING THE SUBJECT WELL LOCATION. THE SUBJECT WELL LOCATION IS CURRENTLY SHUT-IN

PLEASE REFER TO THE ATTACHED CASING LEAK CHRONOLOGICAL HISTORY.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 9/8/2008

(This space for State use only)

RECEIVED

SEP 09 2008

DIV. OF OIL, GAS & MINING

<b>WINS No.: 71806</b>		<b>NBU 438</b>		<b>Start Date: 8/13/2008</b>	
<b>AFE No.: 804019D</b>		<b>Operation Summary Report</b>		<b>End Date:</b>	
<b>Operator</b> KERR MCGEE OIL & GAS ONSHORE LP		<b>FIELD NAME</b> NATURAL BUTTES	<b>SPUD DATE</b> 3/21/05	<b>GL</b> 4,955	<b>KB</b> 4970
<b>API</b> 4304734787		<b>STATE</b> UTAH	<b>COUNTY</b> UINTAH		<b>ROUTE</b> RUN 08
<b>Lat./Long.:</b> Lat./Long.: 39.99389 / -109.56250		<b>Q-Q/Sect/Town/Range:</b> SWNW / 33 / 9S / 21E		<b>Footages:</b> 2,133.00' FNL 986.00' FWL	
<b>MTD</b> 9478	<b>TVD</b> 0	<b>LOG MD</b>	<b>PBMD</b> 9429	<b>PBTVD</b> 9429	
<b>EVENT INFORMATION:</b>		<b>EVENT ACTIVITY:</b> RECOMPLETION		<b>REASON:</b> AFE NO.: 804019D	
		<b>OBJECTIVE:</b> SECONDARY		<b>DATE WELL STARTED/RESUMED:</b>	
		<b>OBJECTIVE2:</b> RECOMPLETE		<b>Event End Status:</b>	
<b>RIG OPERATIONS:</b> Begin Mobilization   Rig On Location   Rig Charges   Rig Operation Start   Finish Drilling   Rig Release   Rig Off Location					
LEED 698 / 698					
<b>Date</b>	<b>Time Start-End</b>	<b>Duration (hr)</b>	<b>Phase</b>	<b>Code</b>	<b>Subcode</b>
<b>P/U</b>					
<b>Operation</b>					
8/13/2008	<u>SUPERVISOR:</u> BRAD BURMAN <span style="float: right;"><u>MD:</u></span>				
	7:00 - 7:30	0.50	WO/REP	48	P JSA #1
	7:30 - 18:30	11.00	WO/REP	30 A	P 7AM [DAY 1]
RDMO CIGE 284. ROAD RIG TO NBU 438. MIRU, SPOT EQUIPMENT. WHP=250#. BLEW WELL DOWN. KILL TBG W/ 20 BBLs. EOT @ 8490'+-. POOH STDG BACK TBG. [SLM] STARTED SEEING PITTED / SCALED TBG & COLLARS @ 1600'. LD 215 JTS BAD TBG ON FLOAT. SEND TBG TO PRS FOR INSPECTION. RETREIVE BUMPER SPRING.  6:30 PM SWI-SDFN. PREP TO RIH W/ GAUGE RING IN AM.					
8/14/2008	<u>SUPERVISOR:</u> BRAD BURMAN <span style="float: right;"><u>MD:</u></span>				
	7:00 - 7:30	0.50	COMP	48	P JSA#2
	7:30 - 15:00	7.50	COMP	37	P 7AM [DAY 2]
SICP=250#. MIRU CUTTERS. RIH W/ 3.625" GAUGE RING TO 7364'. POOH & LD GAUGE RING. RIH W/ BAKER 8K CBP & SET @ 7320'. POOH W/ WL TOOLS. NDBOP, NU FRAC VALVES.  MIRU DBL JACK TESTERS. ATTEMPT TO TEST CSG. PUMP IN @ 3700# @ 1 BPM. CALL TOOL HAND & PKR. RIH W/ SINKER BAR ON W.L. WHILE WAITING FOR PKR. TAG CBP @ 7320'. POOH W/ W.L. TOOLS. RIH W/ PKR & SET @ 1550'. NO TEST. TBG LEAK?  5:30 PM SWI-SDFN. PREP TO POOH LAYING DN OLD TBG & RIH W/ NEW TO TEST IN AM.					
8/15/2008	<u>SUPERVISOR:</u> BRAD BURMAN <span style="float: right;"><u>MD:</u></span>				
	7:00 - 7:30	0.50	COMP	48	P JSA#3
	7:30 -		COMP	30	P 7AM [DAY 3] JSA#3
SICP=250#. RLS PKR @ 1550'. POOH LAYING DN OLD TBG & BHA. PU PKR & NEW 2-3/8" J-55 TBG & RIH. [SLM] TBG WAS DRIFTED. FOUND CSG LEAK BETWEEN 1767'-1798'. POOH LAYING DN TBG & BHA. RD FLOOR & TBG EQUIPMENT. NDBOP, NUWH. RACK EQUIPMENT.  3PM SWI-SDF-WE. WIIL HAVE A DECISION MONDAY 8/18/08 ON WHAT TO DO WITH WELL.					
8/18/2008	<u>SUPERVISOR:</u> BRAD BURMAN <span style="float: right;"><u>MD:</u></span>				
	7:00 - 7:30	0.50	COMP	48	P JSA#4

<b>Wins No.: 71806</b>		<b>NBU 438</b>		<b>API No.: 4304734787</b>																											
<b>EVENT INFORMATION:</b>		EVENT ACTIVITY: RECOMPLETION		REASON:																											
		OBJECTIVE: SECONDARY		DATE WELL STARTED/RESUMED.																											
		OBJECTIVE2: RECOMPLETE		Event End Status:																											
<b>RIG OPERATIONS:</b>		Begin Mobilization Rig On Location Rig Charges		Rig Operation Start Finish Drilling Rig Release Rig Off Location																											
LEED 698 / 698																															
Date	Time Start-End	Duration (hr)	Phase	Code	Subco de	P/U	Operation																								
	7:30 - 15:00	7.50	COMP	33		P	7AM [DAY 4]																								
<p>WE-SICP=50#. 9-5/8" SURFACE CSG SIP=1300#. BLEW SURFACE &amp; 4-1/2" CSG PRESSURES DOWN. PMP DN 4-1/2" CSG &amp; ATTEMPT TO RETURN UP 9-5/8" ANNULUS. PRESSURE UP TO 4000#. 15 MIN LEAK OFF TO 3800#. WORK P.T. UNTILL REACHING 4000# TO 3600# IN 6 MIN. EVENTUALLY GOT TO 3700# @ 1 BPM WITH 25 BBLS INJECTED. PRESSURED BACK UP TO BEGINING INJECTION TEST. ATTEMPT TO REVERSE CIRCULATE DN 9-5/8" UP 4-1/2" CSG. HELD GOOD FOR 15 MIN @ 3000#. CONSULT W/ ENGINEERING. -- CALL FOR PUMP TRUCK TO ATTEMPT TO BRK DN IN AM.</p> <p style="text-align: right;">3 PM SW-SDFN. 50 BBLS TOTAL PMP'D TODAY.</p>																															
<div style="display: flex; justify-content: space-between;"> <span>8/19/2008</span> <span><u>SUPERVISOR:</u> BRAD BURMAN</span> <span><u>MD:</u></span> </div> <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">7:00 - 7:30</td> <td style="width:10%;">0.50</td> <td style="width:10%;">MAINT</td> <td style="width:5%;">48</td> <td style="width:5%;"></td> <td style="width:5%;">P</td> <td style="width:5%;">HLD JSA</td> <td></td> </tr> <tr> <td>7:30 - 15:00</td> <td>7.50</td> <td>MAINT</td> <td>33</td> <td>C</td> <td>P</td> <td>7AM [DAY 4]</td> <td></td> </tr> </table> <p>4-1/2" SICP=10#, 9-5/8" SIAP=0#. WAIT ON WTFRD PUMP TRUCK. MIRU WTFRD. P.T. SURFACE LINES TO 7640#.FOUGHT WTFRD SOFTWARE/COMPUERS 4 HRS. PMP INTO 4-1/2" PROD CSG LEAK BETWEEN 1776'-1798' @ 6292# @ 2 PM.</p> <p>4006# @ 2 BPM @ 5 BBLS PMP'D. 3667# @ 2 BPM @ 10 BBLS PMP'D. 3478# @ 2 BPM @ 15 BBLS PMP'D.- RETURNS TO SURFACE. QUIT GETTING RETURNS @ 18 BBLS GONE 3235# @ 2 BPM @ 20 BBLS PMP'D. 3383# @ 2 BPM @ 25 BBLS PMP'D. 2729# @ 2 BPM @ 30 BBLS PMP'D. 2400# @ 2 BPM @ 35 BBLS PMP'D. ISIP=1300#.</p> <p>MIRU CUTTERS. RIH W/ CBL TOOLS. LOG FROM 2700' TO SURFACE. FOUND A 40' BRIDGE @ 1400'. RDMO CUTTERS.</p> <p style="text-align: right;">5 PM SWI-SDFN. PREP TO SQZ IN AM W/ HLBRTN.</p> <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">15:00 - 15:00</td> <td style="width:10%;">0.00</td> <td style="width:10%;">MAINT</td> <td style="width:5%;"></td> <td style="width:5%;"></td> <td style="width:5%;"></td> <td style="width:5%;"></td> <td></td> </tr> </table>								7:00 - 7:30	0.50	MAINT	48		P	HLD JSA		7:30 - 15:00	7.50	MAINT	33	C	P	7AM [DAY 4]		15:00 - 15:00	0.00	MAINT					
7:00 - 7:30	0.50	MAINT	48		P	HLD JSA																									
7:30 - 15:00	7.50	MAINT	33	C	P	7AM [DAY 4]																									
15:00 - 15:00	0.00	MAINT																													
<div style="display: flex; justify-content: space-between;"> <span>8/20/2008</span> <span><u>SUPERVISOR:</u> BRAD BURMAN</span> <span><u>MD:</u></span> </div> <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">7:00 - 7:30</td> <td style="width:10%;">0.50</td> <td style="width:10%;">COMP</td> <td style="width:5%;">48</td> <td style="width:5%;"></td> <td style="width:5%;">P</td> <td style="width:5%;">JSA--- CEMENTING</td> <td></td> </tr> <tr> <td>7:30 -</td> <td></td> <td>COMP</td> <td>30</td> <td></td> <td>P</td> <td>7AM [DAY 6]</td> <td></td> </tr> </table> <p>P/U 4-1/2" CMT RETAINER &amp; RIH ON NEW 2-3/8" J-55 TBG. [SLM] TBG WAS DRIFTED. SET RETAINER @ 1701'.</p> <p>MIRU HLBRTN. HLD JSA. ESTABLISH INJ RATE @ 3100 @ 2.5 BPM. PMP'D 70 SX LEAD SLURRY, 15.8#, 1.15 YIELD PREMIUM CLASS G CMT. STARTED LOCKING UP @ 65 SX GONE. LOCKED UP @ 70 SX CMT @ 4000#. STING OUT OF CICR LEAVING 2 SX CMT ON TOP. DISPLACE TBG W/ 15 BBLS. R/D HLBRTN. POOH &amp; L/D 2 JTS. CONTINUE POOH STDG BACK TBG. L/D STINGER.</p> <p style="text-align: right;">3 PM SW-SDFN. PREP TO DRILL CICR IN AM.</p>								7:00 - 7:30	0.50	COMP	48		P	JSA--- CEMENTING		7:30 -		COMP	30		P	7AM [DAY 6]									
7:00 - 7:30	0.50	COMP	48		P	JSA--- CEMENTING																									
7:30 -		COMP	30		P	7AM [DAY 6]																									
<div style="display: flex; justify-content: space-between;"> <span>8/21/2008</span> <span><u>SUPERVISOR:</u> BRAD BURMAN</span> <span><u>MD:</u></span> </div> <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">11:00 - 11:30</td> <td style="width:10%;">0.50</td> <td style="width:10%;">COMP</td> <td style="width:5%;">48</td> <td style="width:5%;"></td> <td style="width:5%;">P</td> <td style="width:5%;">JSA DRLG CICR</td> <td></td> </tr> </table>								11:00 - 11:30	0.50	COMP	48		P	JSA DRLG CICR																	
11:00 - 11:30	0.50	COMP	48		P	JSA DRLG CICR																									



<b>Wins No.: 71806</b>		<b>NBU 438</b>		<b>API No.: 4304734787</b>	
<b>EVENT INFORMATION:</b>		EVENT ACTIVITY: RECOMPLETION		REASON:	
		OBJECTIVE: SECONDARY		DATE WELL STARTED/RESUMED:	
		OBJECTIVE2: RECOMPLETE		Event End Status:	
<b>RIG OPERATIONS:</b>		Begin Mobilization	Rig On Location	Rig Charges	Rig Operation Start
		Finish Drilling	Rig Release	Rig Off Location	
LEED 698 / 698					
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode
					P/U
	11:30 -		COMP	44	B
					P
11AM [DAY 7] SICP=0#.					
P/U 3-7/8" BIT, POS W/ XN NIPPLE & RIH ON NEW 2-3/8" J-55 TBG. [SLM] TBG WAS DRIFTED. TAG WET CMT @ 1681'. R/U SWVL & RIG PMP. ESTABLISH CIRCULATION. DRILL OUT 20' WET CMT & CICR IN 4 HRS. CIRC CLN. HARD CMT UNDER CICR.					
5:30 PM SWI SDFN. PREP TO DRILL OUT CMT IN AM.					
8/22/2008	<u>SUPERVISOR:</u> BRAD BURMAN				
	7:00 - 7:30	0.50	COMP	48	P
	7:30 - 15:00	7.50	COMP	44	A
					P
JSA --DRLG CMT					
7AM [DAY 8]					
EOT @ 1700'+-. SICP=0#. ESTABLISH CIRCULATION W/ RIG PUMP. DRILL & C/O 89' CMT TO 1789'. FELL THROUGH. P.T. CSG TO 1000# FOR 15 MIN. [HELD GOOD].					
RIH TO CBP @ 7320'. [SLM] TBG WAS DRIFTED. DRILL OUT 1/2 OF CBP. WELL WENT ON EXTREME VACUM. ATTEMPT TO REGAIN CIRCULATION W/ 100 BBLS. -- NO LUCK. CALL FOR FOAM UNIT FOR MONDAY AM. 8/25/09.					
3 PM SWI-SDF-WE.					
8/25/2008	<u>SUPERVISOR:</u>				
	7:00 - 7:30	0.50	WO/REP	48	P
	7:30 -		WO/REP	30	P
JSA-- AIR FOAM UNITS					
7AM [DAY 9]					
SICP=1600#. EOT @ 7320'+-. BLEW WELL DN. MIRU FOAM TECH AIR FOAM UNIT. ESTABLISH CIRC IN 35 MIN. DRILL OUT REMAINING CBP.					
RIH, [SLM] TBG WAS DRIFTED. TAG FILL @ 9292'. C/O 48' SCALE TO 9340'. WORE OUT BIT. NOT MAKING HOLE. ORIG PBTD @ 9430'. B.P @ 9290'. -- 50' RATHOLE. FCP=300#.					
CIRC WELL CLN. RDMO FOAM TECH. POOH & L/D 20 JTS ON FLOAT. CONTINUE POOH STDG BACK TBG. KILL WELL W/ 30 BBLS. POOH & L/D BHA. FOUND BIT SUB & XN NIPPLE. NO BIT OR BIT SUB.-- PMP'D OFF? P/U XN NIPPLE W/ N.C. & RIH OUT OF DERRICK ON 2-3/8" TBG. LAND TBG ON HNGR W/ 278 JTS NEW 2-3/8" J-55 TBG. EOT @ 8742.52', & XN W/ N.C. @ 8740.32'. KILL WELL W/ 40 BBLS. NDBOP, NUWH. BLOW DN CSG TO GET AIR OUT. RACK EQUIPMENT. LEAVE WELL SHUT IN TO BUILD PSI. RD RIG.					
LTR=0 BBLS.					
6:30 PM SDFN. PREP TO MOVE TO BON 1023-7JT IN AM.					

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: U-015630-ST
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2133' FNL, 986' FWL		8. WELL NAME and NUMBER: NBU 438
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E		9. API NUMBER: 4304734787
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input checked="" type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>RTS - Remedial Cement</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

KERR MCGEE OIL AND GAS ONSHORE LP REQUESTS TO COMMENCE CORRECTIVE ACTIVITIES FOR THE EPA PERMIT NUMBER UT21143-0778.

PLEASE SEE ATTACHED.

**COPY SENT TO OPERATOR**

Date: 11.13.2008

Initials: KS

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 11/6/2008

(This space for State use only)

**APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING**  
DATE: 11/10/08  
BY: [Signature] (See Instructions on Reverse Side)

Federal Approval Of This  
Action Is Necessary

**RECEIVED**

**NOV 10 2008**

**DIV. OF OIL, GAS & MINING**

## APPENDIX F

### CORRECTIVE ACTION REQUIREMENTS

CORRECTIVE ACTION for NBU 921-33F (API 43-047-36391) - Radioactive Tracer Survey (RTS) to prove fluid confinement within the proposed injection interval 1645'-1970':

Perforate 1942' and 1674' w/ 4 SPF  
TIH w/ RPB and Packer  
Set RPB at 2100' and Packer at 1900'  
Conduct RTS to prove fluid confinement above 1970'  
Release Packer  
Reset RPB at 1750' and Packer at 1450'  
Conduct RTS to prove fluid confinement below 1645'  
Remedial Activity will be contingent upon RTS Results  
Squeeze perforations at 1942' and 1674' and return well to production status.

CORRECTIVE ACTION for NBU 396 (API 43-047-34480) - Cement Bond Log (RTS):  
to prove fluid confinement within the proposed injection interval 1660'-1981':

Set RPB at 5300'  
Run CBL from 5300' - Surface  
Remedial Activity will be contingent upon CBL Results

CORRECTIVE ACTION for NBU 438 (API 43-047-34787) - Radioactive Tracer Survey (RTS): to prove fluid confinement within the proposed injection interval 1653'-1966':

Set RPB at 2600' w/ 10' sand on top and test to 3000 psi.  
Perforate 4-1/2" casing at 2450 and establish circulation thru perfs from 2450' - Surface  
Set CICR at 2400' and establish circulation thru perfs from 2450' - Surface  
Cement 4-1/2" x 9-5/8" annulus from 2450' - Surface  
Sting out CICR, Circulate 4-1/2" casing clean, and WOC  
Perforate 1940' and 1670' w/ 4 SPF  
TIH w/ RPB and Packer  
Set RPB at 2100' and Packer at 1900'  
Conduct RTS to prove fluid confinement above 1966'  
Release Packer  
Reset RPB at 1700' and Packer at 1450'  
Conduct RTS to prove fluid confinement below 1653'  
Remedial Activity will be contingent upon RTS Results  
Squeeze perforations at 1940' and 1670' and return well to production status.

ANNUAL TEMPERATURE LOGGING FOR ALL AOR WELLS:

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
KERR MCGEE OIL & GAS ONSHORE LP

3. ADDRESS OF OPERATOR:  
1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-7024

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2133' FNL, 986' FWL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 33 9S 21E

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:  
U-015630-ST

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:  
NATURAL BUTTES UNIT

8. WELL NAME and NUMBER:  
NBU 438

9. API NUMBER:  
4304734787

10. FIELD AND POOL, OR WILDCAT:  
NATURAL BUTTES

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input checked="" type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Remedial Cement
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

KERR MCGEE OIL AND GAS ONSHORE LP REQUESTS TO COMMENCE CORRECTIVE ACTIVITIES FOR THE EPA PERMIT NUMBER UT21143-0778.

PLEASE SEE ATTACHED.

COPY SENT TO OPERATOR

Date: 11.26.2008

Initials: KS

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE *Sheila Upchego me*

DATE 11/6/2008

(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING

DATE: 11/25/08

BY: *[Signature]* (See Instructions on Reverse Side)

(5/2000)

\* Mahogany Bench @ 2350' should be properly isolated

RECEIVED

NOV 12 2008

DIV. OF OIL, GAS & MINING

## APPENDIX F

### CORRECTIVE ACTION REQUIREMENTS

**CORRECTIVE ACTION for NBU 921-33F (API 43-047-36391) - Radioactive Tracer Survey (RTS) to prove fluid confinement within the proposed injection interval 1645'-1970':**

Perforate 1942' and 1674' w/ 4 SPF  
TIH w/ RPB and Packer  
Set RPB at 2100' and Packer at 1900'  
Conduct RTS to prove fluid confinement above 1970'  
Release Packer  
Reset RPB at 1750' and Packer at 1450'  
Conduct RTS to prove fluid confinement below 1645'  
Remedial Activity will be contingent upon RTS Results  
Squeeze perforations at 1942' and 1674' and return well to production status.


**CORRECTIVE ACTION for NBU 396 (API 43-047-34480) - Cement Bond Log (RTS):**  
to prove fluid confinement within the proposed injection interval 1660'-1981':

Set RPB at 5300'  
Run CBL from 5300' - Surface  
Remedial Activity will be contingent upon CBL Results

**CORRECTIVE ACTION for NBU 438 (API 43-047-34787) - Radioactive Tracer Survey (RTS): to prove fluid confinement within the proposed injection interval 1653'-1966':**

Set RPB at 2600' w/ 10' sand on top and test to 3000 psi.  
Perforate 4-1/2" casing at 2450 and establish circulation thru perfs from 2450' - Surface → ?? Cement sqz in Aug 2008 @ 1776-98 w/ 705N @ 4000 psi  
Set CICR at 2400' and establish circulation thru perfs from 2450' - Surface  
Cement 4-1/2" x 9-5/8" annulus from 2450' - Surface  
Sting out CICR, Circulate 4-1/2" casing clean, and WOC  
Perforate 1940' and 1670' w/ 4 SPF  
TIH w/ RPB and Packer  
Set RPB at 2100' and Packer at 1900'  
Conduct RTS to prove fluid confinement above 1966'  
Release Packer  
Reset RPB at 1700' and Packer at 1450'  
Conduct RTS to prove fluid confinement below 1653'  
Remedial Activity will be contingent upon RTS Results  
Squeeze perforations at 1940' and 1670' and return well to production status.

**ANNUAL TEMPERATURE LOGGING FOR ALL AOR WELLS:**

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> U-015630-ST
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 438
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2133 FNL 0986 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWNW Section: 33 Township: 09.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047347870000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input checked="" type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion: 4/21/2009	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input checked="" type="checkbox"/> <b>OTHER</b>	
	<input type="checkbox"/> <b>CASING REPAIR</b>	
	<input type="checkbox"/> <b>CHANGE WELL NAME</b>	
	<input type="checkbox"/> <b>CONVERT WELL TYPE</b>	
	<input type="checkbox"/> <b>NEW CONSTRUCTION</b>	
	<input type="checkbox"/> <b>PLUG BACK</b>	
	<input type="checkbox"/> <b>RECOMPLETE DIFFERENT FORMATION</b>	
	<input type="checkbox"/> <b>TEMPORARY ABANDON</b>	
	<input checked="" type="checkbox"/> <b>WATER DISPOSAL</b>	
	<input type="checkbox"/> <b>APD EXTENSION</b>	
	OTHER: REMEDIAL CEMENT	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>		
THE OPERATOR HAS PERFORMED THE REMEDIAL CEMENT WORK ON THE SUBJECT WELL LOCATION. IN ACCORDANCE WITH THE CORRECTIVE ACTIVITIES FOR THE EPA PERMIT NUMBER UT21143-0778. PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY		
<b>Accepted by the Utah Division of Oil, Gas and Mining</b>		
<b>Date:</b> May 26, 2010		
<b>By:</b> 		
<b>NAME (PLEASE PRINT)</b> Sheila Wopsock	<b>PHONE NUMBER</b> 435 781-7024	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 5/25/2010	

RECEIVED May 25, 2010

US ROCKIES REGION  
Operation Summary Report

Well: NBU 438				Spud Date: 3/21/2005					
Project: UTAH-UINTAH			Site: NBU 438				Rig Name No: SWABBCO 1/1		
Event: RECOMPL/RESEREVEADD			Start Date: 3/24/2009					End Date: 4/21/2009	
Active Datum: RKB @4,969.99ft (above Mean Sea Level)				UWI: NBU 438					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
3/24/2009	7:00 - 7:30	0.50	WO/REP	48		P		HSM. RIGGING UP & TRIPPING PIPE	
	7:30 - 17:30	10.00	WO/REP	30	A	P		ROAD RIG FROM CIGE 114 TO NBU 438. SPOT IN EQUIPMENT. SIC & TP 250 PSI. PUMP 30 BBLS OF 2% KCL DOWN CASING & 20 BBLS DOWN TUBING. WELL DEAD. POOH W/ TBG & TALLY OUT 278 JTS . MIRU CUTTERS TO SET CBP @ 2,609' & RUN CBL FROM 2,609' TO SURFACE. RIH W/ 4 1/2" CBP & SET @ 2,609'. POOH W/ WIRE LINE. FILL CASING W/ 40 BBLS OF 2% KCL WATER. PU CBL TOOLS RIH FOUND FLUID HAD TO MUCH AIR INTRAPED TO RUN CBL. RIH TAG CBP @ 2,609'. POOH W/ CBL TOOLS. PUMP 2% KCL WATER TO CHECK FOR LEAK. PRESSURED UP TO 1,000 PSI HOLDING. SWIN. WILL RUN CBL IN AM.	
TOTAL FLUID PUMPED FOR TODAY 110 BBLS									
3/25/2009	6:30 - 7:00	0.50	COMP	48		P		HSM. WIRE LINE WORK	
	7:00 - 9:00	2.00	COMP	41	A	P		MIRU CUTTERS PU CBL TOOLS RIH TO 2,609' PRESSURE UP CASING TO 1,000 PSI & HOLD PRESSURE. LOG CASING FROM 2,609' TO SURFACE W/ PRESSURE.	
	9:00 - 12:00	3.00	COMP	46	A	P		DOWN LOAD LOG TO PDF FILE & SEND TO ENGINEERING. FOR ORDERS	
	12:00 - 18:00	6.00	COMP	37	B	P		PU 1 9/16" GNS, 3.2 GRM .5 HOLES, 0 DEG PHASING. CASING PUNCH. RIH PERF 2,090' & 1,956'. POOH W/ WIRE LINE. PU 4 1/2" PACKER & RIH W/ 63 TJS OF 2 3/8" J-55 TBG. SET PACKER @ 1,989'. PUMP DOWN TBG @ 1/4 BPM @ 1,800 PSI THRU PERFS @ 2,090, VERY LITTLE RETURNS. PUMED DOWN ANNULUS COULD NOT BRK DOWN PERFS @ 1,956'. RELEASED PACKER & PULLED 3 JTS EOT 1,894'. WAIT ON DUMP BAILER FROM TOWN. PU DUMP BAILER RIH TO 1,955' DUMPED ACID. POOH W/ WIRE LINE. RIH W/ 3 JTS OF TBG SET PACKER @ 1,989'. PUMP DOWN TGB CASING ANNULUS PRESSURED UP TO 4,000 PSI COULD NOT GET A BRK. BLEED OFF PRESSURE SWIFN.	
3/26/2009	6:30 - 7:00	0.50	COMP	48		P		HSM. CEMENTING & PERFORATING & RUNNING TOOLS	

US ROCKIES REGION  
Operation Summary Report

Well: NBU 438

Spud Date: 3/21/2005

Project: UTAH-UINTAH

Site: NBU 438

Rig Name No: SWABBCO 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 3/24/2009

End Date: 4/21/2009

Active Datum: RKB @4,969.99ft (above Mean Sea Level)

UWI: NBU 438

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:00 - 17:00	10.00	COMP	40	A			<p>PUMP DOWN CASING PRESSURE UP TO 4,000 PSI COULD NOT GET A BRK DOWN.</p> <p>RELEASE PACKER POOH W/ 3 JTS EOT TBG @ 1,895'.</p> <p>PU 1 9/16" GNS, 3.2 GRM, .5 HOLES O DEG PHASING. .5" PENETRATION.</p> <p>RIH PERF 1,956 AGAIN. 4 HOLES.</p> <p>WIRE LINE DEPTH DIFFERED FROM TBG TALLY BY 47'. POOH W/ WIRE LINE.</p> <p>RIH W/ 4 JTS SET PACKER @ 2,019' TBG = 1,972' WIRE LINE DEPTH.</p> <p>PUMP DOWN TBG HAD RETURNS PUMPING 1 BPM @ 800 PSI.</p> <p>RELEASE PACKER POOH W/ 32 STANDS.</p> <p>PU 4 1/2" CICR RIH SET @ 2,019'. MIRU BIG 4 CEMENTERS.</p> <p>HOLD SAFETY &amp; SERVICE MEETING.</p> <p>PUMP 10 BLS FRESH WATER @ .8 BPM @ 900 PSI.</p> <p>START CMT PMP 65 SKS OF CLASS G 2% CACL2 WT 15.8 PPG, YIELD 1.15 CU FT/SK WATER 4.97 GAL/SK. 13 BLS OF SLURRY.</p> <p>DISPLACE W/ 8 BLS FRESH WATER. PUMPED 1.25 BPM @ 1,800 PSI.</p> <p>UN STING OUT OF RETAINER &amp; REVERSE CIRC. PUMPED 6 BLS OF CMT TO SURFACE.</p> <p>POOH W/ TBG. PU 1 9/16" GNS RIH PERF 1,516' 4 SPF, 1,445' 4 SPF. CASING PUNCH.</p> <p>RIH W/ PACKER W/ 24 STANDS SET PACKER @ 1,517' TBG 1,471 WIRE LINE DEPTH.</p> <p>BRK CIRC 1 BPM @ 1,000 PSI. POOH W/ PACKER. PU CICR RIH W/ 24 STANDS. CEMENT RET @ 1,516' TBG TALLY 1,471 WIRE LINE.</p> <p>PUMP 10 BLS FRESH WATER AHEAD.</p> <p>PUMP 30 SKS CLASS G 2% CACL2 WT 15.8 PPG YIELD 1.15 CU FT/SK WATER 4.97 GAL/SK. 6 BLS SLURRY.</p> <p>PUMPED @ 1.25 BPM @ 1,250 PSI. DISPLACED W/ 5.7 BLS.</p> <p>UN STING FROM RETAINER. REVERSE CIR HAD 3 BLS CEMENT TO SURFACE.</p> <p>POOH W/ TUBING. SWI SDFN</p>
3/27/2009	7:00 - 7:30	0.50	COMP	48		P		<p>HSM. COLD WEATHER WATCH FOR FROZEN PUMPS &amp; LINES.</p>



US ROCKIES REGION  
Operation Summary Report

Well: NBU 438

Spud Date: 3/21/2005

Project: UTAH-UINTAH

Site: NBU 438

Rig Name No: SWABBCO 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 3/24/2009

End Date: 4/21/2009

Active Datum: RKB @4,969.99ft (above Mean Sea Level)

UWI: NBU 438

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:30 - 15:00	7.50	COMP	40	A			PU 1 9/16" GNS 3.2 GRM, .5 HOLES, 0 DEG PHASING. RIH PERF 1,340' 4 SPF, 4 HOLES. PUMP DOWN 4 1/2" CASING & OUT OUT 9 5/8" CASING @ 1/2 BPM @ 1,300 PSI. GETTING MUD FOR RETURNS PUMP 50 BBLS OF WATER TO CLEAN OUT ANNULUS. PU 4 1/2" PACKER RIH W/ 17 STANDS SET PACKER @ 1,078'. RU BIG 4 CEMENTERS PUMP INTO PERFS @ 3/4 BPM @ 1,800 PSI. DECIDED TO USE CICR. POOH W/ TBG. PU CICR RIH SET @ 1,297' PMP DON TBG USING BIG 4. PUMP 95 SKS OF CLASS G CEMENT, WT 15.8 PPG, YIELD 1.15 CU FT/SK, WATER 4.97 GAL/SK = 19.5 BBLS. PUMPED CEMENT @ 1/2 BPM @ 1,900 PSI. HAD CEMENT TO SURFACE AFTER PUMPING 75 SKS. 4 BBLS CEMENT TO SURFACE. DISPLACED W/ 4 BBLS PRESSURE WAS UP TO 2,100 PSI @ 1/3 BPM. UN STING FROM CICR LD 1 JT & REVERSE CIRC TBG CLEAN. RDMO BIG 4. POOH W/ TUBING. SWIFWE. WILL DRL CEENT ON MONDAY
3/30/2009	7:00 - 18:00	11.00	WO/REP	30		P		HSM TIH 3 7/8 BIT, 10 3 1/8 DRILL COLLARS & 31 JNTS TAG CEMENT @ 1262' P/U SWIVEL WITH JNT 31 DRILL CEMENT TO CICR @ 1297' DRILL ON CICR DRILL UP IN 6HRS DRILL ON CEMENT VERY HARD DRILL TO 1327' DRAIN UP SWI SDFN
3/31/2009	7:00 - 18:00	11.00	WO/REP	30		P		HSM DRILL CEMENT TO 1370' = 30' PAST PERFS @ 1340' TEST CSG TO 1000 PSI = GOOD TEST HUNG SWIVEL TOH CHANGE BIT TIH TAG CEMENT @ 1450' DRILL CEMENT TO CICR @ 1516' DRILL ON CICR 4 HRS SWI SDFN
4/1/2009	7:00 - 18:00	11.00	WO/REP	30		P		HSM FINISH CICR DRILL CEMENT TO 1548' = 30' PAST PERFS TEST CSG TO 1000 PSI = GOOD TEST HUNG SWIVEL TOH CHANGE BIT TIH TAG CEMENT @ 1980' P/U SWIVEL WITH JNT 54 DRILL CEMENT TO CICR @ 2019' DRILL UP CICR IN 4 1/2 HRS DRILL CEMENT TO 2072' SWI SDFN
4/2/2009	7:00 - 17:30	10.50	WO/REP	30		P		HSM DRILL CEMENT TO 2130' = 40' PAST PERFS SWIVEL IN TO 2230 TEST CSG TO 1000 PSI = GOOD TEST HUNG SWIVEL TOH TBG LD 6 COLLARS WELL STARTED PUSHING FLUID @ SURFACE LD LAST 4 COLLARS SWI OPEN TO TANK WELL UNLOADED ALL FLUID FROM CSG BRINGING UP LARGE PIECES OF CICR = CBP LEAKING SWI R/U CUTTERS WAIT ON CBP KILL WELL RIH SET 5K CBP @ 2642' POOH TIH 41 STANDS TO 2580' ROLL HOLE WITH FRESH WATER TEST CSG & PLUG TO 1000 PSI = GOOD TEST TOH R/U CUTTERS RIH RUN CBL FROM 2600' TO SURFACE SWI SDFN

US ROCKIES REGION  
Operation Summary Report

Well: NBU 438

Spud Date: 3/21/2005

Project: UTAH-UINTAH

Site: NBU 438

Rig Name No: SWABBCO 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 3/24/2009

End Date: 4/21/2009

Active Datum: RKB @4,969.99ft (above Mean Sea Level)

UWI: NBU 438

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
4/3/2009	7:00 - 18:00	11.00	WO/REP	30		P		HSM R/U CUTTERS PERF 4SPF @ 1940' & 1670' TIH 4 1/2 RBP & PKR SET RBP @ 2090' & PKR @ 2020' TEST TOOLS TO 2000PSI = GOOD TEST SET PKR @ 1894 ATTEMPT TO BREAK DOWN PERFS @ 1940' UNABLE TO BREAK DOWN BEST INJ RATE OF 1/4 BPM @ 3700 PSI CSG STARTED TO FLOW A LITTLE WHILE PUMPING = COMMUNICATION BETWEEN PERFS RELEASE & RESET PKR @ 1455' BREAK DOWN UPPER PERFS @ 1670 WITH 2700 PSI EST INJ OF 1/2 BPM @ 700 PSI TOH TBG & PKR RIH DUMP BAIL 5 GAL 15% ACID @ 1840' = 100' ABOVE PERFS POOH TIH SET PKR @ 1831' WITH 58 JNTS PUMP ACID TO PERFS BROKE DOWN TO 1200 PSI STARTED TO COMMUNICATE WITH UPPER PERFS SHUT PIPE RAMS STOP PUMPING LET ACID SET IN PERFS FOR 5 MIN PRESSURE DROPPED TO 800 PSI STARTED PUMPING 1/2 BPM @ 1200 PSI P/3 BBLs & LOCKED BACK UP TO 1/4 BPM @ 3500 PSI WORK PRESSURE FROM 0-3500 PSI SEVERAL TIMES UNABLE TO GET PERFS TO BREAK DOWN DECIDED TO RUN RATS TEST ON UPPER PERFS ATTEMPT TO RELEASE PKR UNABLE TO GET ANY MOVEMENT TO PKR ATTEMPT TO BACK OUT OF SAFETY WITH RIGHT HAND TURNS WITH TONGS PUT A TOTAL OF 8 ROUNDS INTO PIPE WITH NO LUCK SAFETY THREADS FLAT THREADED & 8 ROUNDS = TIGHTENING TBG NOT GETTING TO PKR WAIT ON FREE POINT TOOLS POSSIBLY PUMPED SOMETHING IN ON TOP OF US THRU TOP PERFS R/U CUTTERS RIH FREE POINT PIPE TBG 100% FREE 5' ABOVE PKR POOH RIH MAKE CHEMICAL CUT @ 1816' = 15' OF TBG ABOVE PKR POOH TOH TBG SWI SDFWE
4/6/2009	7:00 - 10:00	3.00	WO/REP	30		X		HSM BWD TIH 3 7/8 OVERSHOT, EXT BOWL, BUMPER SUB, 2 3 1/8 COLLARS, X-OVER & 55 JNTS STACK OUT @ 1795' = 21' ABOVE FISH TOP @ 1816' & 36' ABOVE PKR @ 1831' TOH TBG & TOOLS WAIT ON WIRELINE
	10:00 - 14:30	4.50	WO/REP	34	G	X		R/U CUTTER WIRELINE, RIH W/ 3-1/8" GAUGE RING, TAG @ 1795', RIH W/ 1-11/16" GAUGE RING SET DN @ 1805', WORK TOOL W/ SET DN AT 1805', RIH W/ 2-1/8" IMPRESSION BLOCK, SET DN @ 1805', P/O SHOWED CUT TBG OVER TO ONE SIDE?, RIH W/ 1-3/4" BLOCK, SET DN @ 1805', R/D WIRELINE
	14:30 - 17:00	2.50	WO/REP	31	I	X		P/U 3-5/8 SLEDGE TOOL RIH W/ DC & TBG SET DN @ 1795' TBG TALLY, SET DN SOILD, TOOH, NO MARK ON TOOL, SHUT WELL IN SDFN
4/7/2009	7:00 - 7:15	0.25	WO/REP	48		X		JSA-SAFETY MEETING #11, DAY 11

US ROCKIES REGION  
Operation Summary Report

Well: NBU 438

Spud Date: 3/21/2005

Project: UTAH-UINTAH

Site: NBU 438

Rig Name No: SWABBCO 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 3/24/2009

End Date: 4/21/2009

Active Datum: RKB @4,969.99ft (above Mean Sea Level)

UWI: NBU 438

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:15 - 16:00	8.75	WO/REP	31	I	X		NO PRESSURE ONWELL, P/U RIH W/ 3-1/2" IMPRESSION BLOCK, TAG AT 1809', TOOHS SHOWED CUT OFF TBG ON BOTTOM, SIDE HAS 1/2" WIDE BY 1/4" DEEP MARK DN BLOCK, P/U 3-5/8" SWEDGE TIH TAG @ 1795' FELL ON DN TO 1809', TOOHS, P/U 3-3/4" SWEDGE TIH TAG @ 1795', WORK THRU TIGHT SPOT @ 1', RIH TO 1809', TOOHS, P/U 3-7/8" SWEDGE TIH TAG @ 1795', SWEDGE OUT CSG FOR 1', TAG TBG AT 1809', TOOHS, P/O 3-3/4" OVERSHOT TIH LATCH ONTO FISH, JAR DN ON TOOLS, PACKER RELEASE, TOOHS W/ SWAB WELL W/ PACKER, P/O SLOW, LAY DN DC, AND FISHING TOOLS, LAY DNCUT OFF JTS AND ;PACKER,
	16:00 - 17:00	1.00	WO/REP	34	H	P		R/U CUTTER WIRELINE RIH PERF 4-1/2"CSG @ 1935', R/D WIRELINE, SWIFN.
4/8/2009	7:00 - 7:15	0.25	WO/REP	48		P		JSA-SAFETY MEETING #12, DAY 12
	7:15 - 12:00	4.75	WO/REP	34		P		NO PRESSURE ON WELL, R/U WIRELINE RIH DUMP BAIL ACID ACROSS PERF, R/D WIRELINE, P/U 4-1/2" PACKER TIH SET PACKER @ 1768', TRY TO PUMP INTO PERF W/ PRESSURE UP TO 3000# BLEED BACK TO 1000#, R/U WIRELINE RIH DUMP 2-1/2 GALS ACID ACROSS PERF, TRY TO PUMP INTO W/ PRESSURE TO 2800# 1/4 B/M, RIH DUMP BAIL 2-1/2 GALS ACID ACROSS PERF, BREAK DN PERF W/ PRESSURE @ 2800# W/ COME DN TO 1500# @ 1/2 B/M, R/D CUTTER WIRELINE.
	12:00 - 14:30	2.50	WO/REP	41	D	P		R/U PRODUCTION LOGGING SERVICE, RIH W/ RTS LOG, RUN RTS FROM 1500' TO 1935', BOTTOM LUID IS CONFINEMENT TO 1935' ONLY, R/D WIRELINE,
	14:30 - 16:00	1.50	WO/REP	31	I	P		P/U ON TBG RELEASE PACKER TOOHS W/ 2-3/8" TBG & PACKER, PU RBP TIH W/ TBG & PACKER, SET RBP @ 1728', P/U SET PACKER @1406',
	16:00 - 18:30	2.50	WO/REP	41	D	P		R/U PRODUCTIONLOGGING SERVICE, RIH W/ RTS LOG TOOL, BROKE DN PERF @ 1632' 1/2B/M @1500#, RUN RTS FROM 1200' TO 1720', TOP IS CONFINEMENT TO 1635' ONLY, R/D WIRELINE, SHUT WELL IN SDFN
4/9/2009	7:00 - 7:15	0.25	WO/REP	48		P		JSA-SAFETY MEETING #13, DAY 13
	7:15 - 8:00	0.75	WO/REP	31	I	P		NO PRESSURE, RELEASE PACKER TIH RETRIVE RBP, TOOHS LAY TOOLS DN, P/U 4-1/2" CICR TIH SET CICR @ 1768',
	8:00 - 10:00	2.00	WO/REP	40	A	P		R/U PRO PETRO CEMENTERS, PUMP IN RATE OF 3/4 B/M @ 1500#, MIX AND PUMP 50 SACKS CLASS G NEAT CEMENT, SLOW DN RATE W/ 2 BBL CMT IN TBG, SQUEEZE OFF PERF @ 1200#, STUNG OUT OF RETAINER W/ DROP @ 1/8 BBBL ON TOP,
	10:00 - 15:00	5.00	WO/REP	31	I	P		TOOHS W/ STINGER, P/U 4-1/2" PACKER TIH SET PACKER @ 1456', R/U CEMENTER, PUMP IN RATE @ 3/4 B/M @ 1500#, MIX AND PUMP 50 SACKS CEMENT, FLUSH CEMENT PASS PACKER, STAGE CEMENT W/ SQUEEZE OFF @ 1000# W/ 1-1/4 BBL CEMENT STILL IN CSG, SHUT WELL IN, SDFWE,

US ROCKIES REGION  
Operation Summary Report

Well: NBU 438

Spud Date: 3/21/2005

Project: UTAH-UINTAH

Site: NBU 438

Rig Name No: SWABBCO 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 3/24/2009

End Date: 4/21/2009

Active Datum: RKB @4,969.99ft (above Mean Sea Level)

UWI: NBU 438

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
4/13/2009	7:00 - 18:00	11.00	WO/REP	30		P		HSM RELEASE & TOH PKR TIH 3 7/8 BLADDE BIT TAG CEMENT @ 1540' P/U SWIVEL WITH JNT 49 DRILL CEMENT TO 1680' WITH JNT 55 = 10' PAST PERFS TEST CSG TO 1000 PSI = GOOD TEST HUNG SWIVEL TOH CHANGE BIT TO 3 7/8 ROCK BIT TIH TAG CEMENT @ 1720' DRILL CEMENT TO CIRC @ 1767' DRILL ON CIRC SWI SDFN
4/14/2009	7:00 - 18:00	11.00	WO/REP	30		P		HSM DRILL UP CIRC DRILL CEMENT TO 1940' = 5' PAST 2ND SET OF PERFS @ 1935' & RIGHT @ ORIGNAL PERFS @ 1940' TEST CSG TO 1000 PSI 3 TIMES HELD 10 MIN GAINED 30 TO 50 PSI EVERY TIME = PERFS LEAKING OR CBP LEAKING BELOW HUNG SWIVEL LD 15 JNTS BACK ON TRAILER TIH 7 STANDS = 62 JNTS IN WELL TAG FILL ABOVE RBP @ 2005' CLEAN OUT TO RBP @ 2090' WITH JNT 66 RETURNS HAD OLD CEMENT, FORMATION ROCKS, & LOST CIRC MATERIAL (CEDER FIBER & CELAFLAKE) HUNG SWIVEL TOH TIH RETRIEVING TOOL & 66 JNTS P/U SWIVEL CIRC OVER STEM LATCH & RELEASE PLUG TOH LD PLUG TIH PKR & 66 JNTS SET PKR @ 2083' = BELOW ALL PERFS TEST CSG TO 1000 PSI = FAILED TEST LOST 30 PSI IN 15 MIN TEST BELOW PKR TO CBP TO 1000 PSI = PLUG LEAKING LOST 100 PSI IN 10 MIN RELEASE PKR PULL 4 JNTS SET PKR @1957' TEST CSG TO 1000 PSI = FAILED BLEED CSG TO 0 PSI PRESSURE BLOW PKR TO 1000 PSI GAINED 240 PSI IN CSG ABOVE PKR= PERFS @ 1981 & 1940 OPEN & COMMUNICATING RELEASE PKR SET @ 1894' TEST CSG TO 1000 PSI = GOOD TEST
4/15/2009	7:00 - 17:00	10.00	WO/REP	30		P		HSM TOH PKR R/U WIRELINE RIH SET 5K CBP @ 2100' LOG UP HOLE SHOWS PERFS @ 1973' & 1940' POOH TIH PKR & 64 JNTS SET PKR @ 2020' TEST PLUG TO 1500 PSI = GOOD TEST RESET PKR @ 1957' WITH 62 JNTS TRY TO EST COMMUNICATION PERFS @ 1973' HELD 1800 PSI 20 MIN RESET PKR @ 1894' WITH 60 NTS PERFS @ 1940' OPEN BUT VERY TIGHT PRESSURE UP TO 2000 PSI LOST 900 PSI IN 15 MIN RELEASE PKR TOH R/U WIRELINE DUMP BAIL 6 GAL ACID @ 1920' = 20' ABOVE PERFS POOH TIH SET PKR @ 1894' TRY TO BREAK DOWN PERFS WITH NO LUCK TOH RIH DUMP 6 GAL ACID ACROSS PERFS TIH SET PKR 1894' STILL UNABLE TO BREAK DOWN PERFS TOH PKR TIH OPEN ENDED TO 2015' CIRC ACID OUT OF HOLE P/15 SKS = 3 BBLs 2% CEMENT BALANCE FROM 2015' TO 1822' = 118' OVER PERFS @ 1940' TOH 4 STANDS TO 1763' TRY TO REV CIRC HOLE TBG PLUGGED TOH HAD 14 JNTS FULL OF CEMENT = 1.7 BBLs OF CEMENT PRESSURE CSG UP TO 400 PSI SWI SDFN
4/16/2009	7:00 - 13:00	6.00	WO/REP	30		P		HSM TIH TAG CEMENT @ 1956' = 16' BELOW PERFS @ 1940' DRILL CEMENT TO 2015' CEMENT GREEN TOH TIH 64 JNTS TO 2015' P/15 SKS G-NEAT = 3BBLs FLUSH WITH 6 BBLs CEMENT TOP @ 1822' TOH 4 STANDS TO 1768' REVERSE CIRC HOLE CLEAN TOH TIH PKR & 58 JNTS SET @ 1768' WORK CEMENT SQUEEZE OUT @ 1250 PSI WITH 1/2 BBL INTO PERFS SWI WITH 1000 PSI SDFWE

US ROCKIES REGION  
Operation Summary Report

Well: NBU 438

Spud Date: 3/21/2005

Project: UTAH-UINTAH

Site: NBU 438

Rig Name No: SWABBCO 1/1

Event: RECOMPL/RESEREVEADD

Start Date: 3/24/2009

End Date: 4/21/2009

Active Datum: RKB @4,969.99ft (above Mean Sea Level)

UWI: NBU 438

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
4/20/2009	7:00 - 17:30	10.50	WO/REP	30		P		HSM RELEASE & TOH PKR TIH 3 7/8 BLADE BIT TAG CEMENT @ 1812' WITH JNT 58 P/U SWIVEL DRILL CEMENT TO 2020' TEST CSG TO 1000 PSI HELD 20 MIN = GOOD TEST TOH CHANGE BIT TIH TAG CBP @ 2100' WITH JNTS 67 P/U SWIVEL DRILL UP CBP IN 1 1/2 HRS HUNG SWIVEL TIH TAG CBP @ 2642' WITH JNT 84 P/U SWIVEL DRILL UP CBP IN 30 MIN HAD 900 PSI BELOW UNLOADED ALL FLUID TO TANK FLOW WELL TO TANK FOR 2 HRS KILL TBG SWIVEL IN TO 2700' PLUG @ 2655' WAS GONE HUNG SWIVEL LD 4 JNTS TIH TO 7608' WITH 242 JNTS = 106' ABOVE TOP PERF SWI SDFN
4/21/2009	7:00 - 16:30	9.50	WO/REP	30		P		HSM TIH TAG @ 9348' = 58' OF RAT HOLE LD 35 JNTS WORK STRING TOH TIH NOTCHED X-NIPPLE & 278 JNTS LTBG @ 8746' R/U SWAB BROACH TBG R/D SWAB NDBOP NUWH SWI FOR 24 HR SHUT IN FOR TEMP LOG R/O PUMP & TANKS RDMO 15 BBLS LEFT TO RECOVER